

RURAL MUNICIPALITY OF MOUNTAIN VIEW NO. 318

ZONING BYLAW

Prepared for:

THE RURAL MUNICIPALITY OF MOUNTAIN VIEW NO. 318

Prepared by:

CROSBY HANNA & ASSOCIATES
LANDSCAPE ARCHITECTURE AND PLANNING
Saskatoon, SK

SEPTEMBER 2019



The Rural Municipality of Mountain View No. 318

Bylaw No. 01-19

A Bylaw of the Rural Municipality of Mountain View No. 318 to adopt a Zoning Bylaw.

The Council of the Rural Municipality of Mountain View No. 318, in the Province of Saskatchewan, in open meeting assembled enacts as follows:

- (1) Pursuant to Section 34(1) of *The Planning and Development Act, 2007* the Council of the Rural Municipality of Mountain View No. 318 hereby adopts the Rural Municipality of Mountain View No. 318 Zoning Bylaw, identified as Schedule "A" to this Bylaw.
- (2) The Reeve and Administrator of the Rural Municipality of Mountain View No. 318 are hereby authorized to sign and seal Schedule "A" which is attached to and forms part of this Bylaw.
- (3) Bylaw No. 05-14 the Zoning Bylaw of the Rural Municipality of Mountain View No. 318, and all amendments thereto, are hereby repealed.
- (3) This Bylaw shall come into force on the date of final approval by the Minister of Government Relations.


Read a first time the 22 day of October, 2019

Read a second time the 10 day of December, 2019

Read a third time the 10 day of December, 2019

Adoption of Bylaw this 10 day of December, 2019


(Reeve)


(Administrator)



Certified a True Copy of the Bylaw adopted by Resolution of Council

On the 10 day of December, of the year 2019



THE RURAL MUNICIPALITY OF MOUNTAIN VIEW NO. 318
ZONING BYLAW

Being Schedule "A" to Bylaw No. OJ - 19
of the Rural Municipality of Mountain View No. 318

Rochelle
(Reeve)

Rachael Duebald
(Administrator)



APPROVED
REGINA, SASK.

JUN 02 2020

[Signature]
Executive Director, Community Planning
Ministry of Government Relations

June 2, 2020

Rachel Deobald, Administrator
RM of Mountain View No. 318
Box 130
HERSCHEL SK S0L 1L0

Dear Rachel Deobald:

**RE: RM of Mountain View No. 318
Bylaw No. 01-2019
New Zoning Bylaw**

Enclosed is a copy of Bylaw No. 01-2019, the zoning bylaw for the RM of Mountian View No. 318, for your records. This bylaw is approved in part as provided for under subclause 37(1)(c) and section 76 of *The Planning and Development Act, 2007* (PDA). As a result of our decision portions of the following subsections have been removed from the approved bylaw.

- Subsection 4.13.17(1)(e) the following wording shall be deleted: "...where the applicant submits a copy of the agreement between the developer of a wind turbine and the Non-Participating Noise Receptor, agreeing to a lesser separation. Such agreements must contain the provision that parties to the agreement will register an interest on the titles of the affected land. Where such agreements are made, Council shall be a party to the agreement and may use Section 235 of *The Act* to register an interest to the title(s) of the affected lands."
- Subsection 4.13.18(1)(e) the following wording shall be deleted: "...where the applicant submits a copy of the agreement between the developer of a wind turbine and the Non-Participating Noise Receptor, agreeing to a lesser separation. Such agreements must contain the provision that parties to the agreement will register an interest on the titles of the affected land. Where such agreements are made, Council shall be a party to the agreement and may use Section 235 of *The Act* to register and interest to the title(s) of the affected lands."

- Subclause 4.13.22(2)(a)(i) the following wording shall be deleted: “.....where the applicant submits a copy of an agreement between the operator of the livestock facility and the owner(s) of the other affected development tor urban Council (as appropriate), agreeing to such lesser separation. Such agreements between an operator and an owner (owners) of another development (other developments) must contain the provision that the parties to the agreement will register an interest to the Titles of the affected land. Where such agreements are made, Council shall be a party to the agreement and may use Section 235 of *The Act* to register an interest to the title(s) of the affected land.”

The above wording has been removed as the manner in which the sections are written would effectively delegate council's decision-making authority to the public. In making council's decision to reduce separation distances conditional upon receiving an agreement from affected landowners or not, it:

- a) restricts council from taking other factors into consideration that may be pertinent to such a decision, and
- b) binds council into making a decision they otherwise may not have.

These deletions allow the bylaw to be more flexible. They grant council enhanced opportunity to consider other factors when determining if reducing separation distances in any given scenario is a sound and reasonable decision. Removing the condition that an agreement must be presented to council in order to relax separation distances, ensures that council retains their decision-making authority.

We further note the following matter for consideration and amendment at a later date. In the A-Agricultural District, Table 6-1 Municipal, Recreational, Institutional and Other Uses (15) lists “Telecommunications facilities” as a discretionary land use and the bylaw also includes a definition for that use. Under the PDA telecommunication facilities are included in the definition for “public works” and as such, are included in the zoning bylaw under the “public works” definition. The bylaw lists “public works” as a permitted land use in that zoning district.

Including the same land use under two separate definitions and attempting to regulate it as two separate land uses, creates conflict within the bylaw and frustrates the ability to effectively administer the bylaw. Telecommunication facilities are a public work and provide a public service regulated by the federal government. They ought to be permitted in all districts in order to facilitate the effective and predictable regulation of telecommunication services for the public interest. The location and installation of telecommunication facilities falls under federal jurisdiction and legislation. While a municipality may engage with the service providers and collaborate to influence optimal

Rachel Deobald

Page 3

June 2, 2020

locations and mitigate any local concerns, a local government does not have the authority to regulate telecommunications as a discretionary use.

I appreciate the time and effort that you and your council have contributed on behalf of your municipality in developing this important document and in ensuring that the legislated procedures are adhered to.

Ministry staff is committed to providing advice on technical matters and assistance in undertaking discussions and directions to be reflected in the bylaw. I would invite you to contact Riley Stefanik, Planning Consultant at 306-933-5215, or John Guenther, Director, at 306-933-6118 to discuss this further or if you have any questions.

Sincerely,



Ralph Leibel

Executive Director

Enclosure

cc: John Guenther, Community Planning, Government Relations
Riley Stefanik, Community Planning, Government Relations

TABLE OF CONTENTS

1	INTRODUCTION	1
1.1	Title	1
1.2	Scope.....	1
1.3	Purpose.....	1
1.4	Severability	1
2	INTERPRETATION.....	3
3	ADMINISTRATION.....	23
3.1	Development Officer.....	23
3.2	Application for Development Permit.....	23
3.3	Developments Not Requiring A Development Permit	23
3.4	Other Permit Requirements.....	24
3.5	Application Requirements.....	24
3.6	Development Permit Application Process.....	28
3.7	Discretionary Use Applications	29
3.8	Validity of a Development Permit.....	39
3.9	Amending the Zoning Bylaw	39
3.10	Development Appeals Board	39
3.11	Minor Variances	39
3.12	Fees	40
3.13	Zoning by Agreement	41
3.14	Offences and Penalties	41
4	GENERAL REGULATIONS	43
4.1	Frontage on the Road	43
4.2	Development on Hazard Lands	43
4.3	Building to be Moved	44
4.4	Waste Disposal	44
4.5	Water	44
4.6	Storage of Chemicals, Fertilizers and Combustible Materials	44
4.7	One Principal Building Permitted on a Site	44
4.8	Non-Conforming Buildings, Sites and Uses	45
4.9	Manufactured Homes	45
4.10	Public Works, Pipelines and Facilities of the Municipality	45
4.11	Vehicle Storage	45
4.12	Manure Disposal	46
4.13	Special Standards and Regulations	46
4.14	Setback from Centre Line of Roads	60
4.15	Outside Storage and Waste Material Storage	60
4.16	Permitted Yard Encroachments	60
4.17	Prohibited Uses in All Districts	61
4.18	Building Lines.....	61
4.19	Bare Land Condominiums	61
4.20	Depth to Frontage Ratio	61
4.21	Temporary Uses	61
4.22	Shipping Containers	62

4.23	Regulations for Signs and Billboards.....	63
5.1	Classification of Zoning Districts	65
5.2	Zoning District Maps	65
5.3	Boundaries	65
5.4	Regulations	65
5.5	Properties with More than One Zoning District	99
5.6	Transitional Zoning Provisions	99
6.1	A-Agriculture District.....	67
6.2	CRI - Low Density County Residential District.....	77
6.3	CR2 - Medium Density County Residential District	81
6.4	H - Hamlet District.....	85
6.5	C1 - Commercial District	91
6.6	MI - Industrial District.....	99
7	REQUIRED SEPARATION DISTANCES BETWEEN USES	105
8	MAPS	107

1 INTRODUCTION

1.1 TITLE

This Bylaw shall be known as the "Zoning Bylaw of the Rural Municipality of Mountain View No. 318".

1.2 SCOPE

All development within the limits of the municipality shall be in conformity with the provisions of this bylaw, subject to the right of appeal provisions of *The Planning and Development Act, 2007 (The Act)*.

1.3 PURPOSE

This is a Bylaw to control the use and development of the land in the municipality and assist in implementing the Rosetown Hub and Spoke District Official Community Plan, which applies to the Rosetown Hub and Spoke Planning District. The municipalities involved in this regional initiative are the Rural Municipalities of St. Andrews No. 287, Pleasant Valley No. 288, Harris No. 316, Marriott No. 317, Mountain View No. 318, the Town of Rosetown, the Village of Harris and the Hamlets of Herschel, Stranraer, Fiske, and Sovereign. This bylaw is consistent with the policies and the intent of the Rosetown Hub and Spoke District Official Community Plan.

1.4 SEVERABILITY

If any part of this Bylaw, including anything shown on the Zoning District Map, is declared to be invalid for any reason, by an authority of competent jurisdiction, that decision shall not affect the validity of the Bylaw as a whole, or any other part, section or provision of this Bylaw.

2 INTERPRETATION

Whenever in this bylaw the following words or terms are used, they shall, unless the context otherwise provides be held to have the following meaning:

Accessory Building or Use: a building or use which:

- (a) is subordinate to and serves the principal building or principal use;
- (b) is subordinate in area, extent and purpose to the principal building or principal use served;
- (c) contributes to the comfort, convenience or necessity of occupants of the principal building or principal use served; and,
- (d) is located on the same site as the principal building or principal use served.

Act, The: *The Planning and Development Act, 2007*, as amended.

Administrator: the Administrator of the RM of Mountain View No. 318.

Agricultural Service and Contracting Establishments: premises used for the supply of goods, materials or services that support agricultural uses including the sale and storage of seeds, feed, fertilizer and chemical products and the rental, sale, repair or service of agricultural equipment or implements and any combination of the foregoing.

Agricultural Support Services: includes,

- (a) grain and seed storage, cleaning and drying;
- (b) fertilizing mixing sales (subject to provincial regulations);
- (c) livestock and poultry breeding services;
- (d) abattoirs;
- (e) bin yards, commercial and farm related; and,
- (f) other agriculturally related services.

Alteration: any structural change or addition made to any building or structure.

Ancillary Use: a use that is secondary and subordinate in size, extent and purpose to the principal use on the same site, but is not necessary for the operation of the principal use on that site.

Animal, Exotic: any animal that is not domesticated in Saskatchewan and is wild by nature.

Animal Unit: the kind and number of animals calculated in accordance with the following:

Kind of Animal	Number Equaling One Animal Unit
(1) <u>Poultry</u>	
(a) hens, cockerels, capons	100
(b) chicks, broiler chicks	200
(c) turkeys, geese, ducks	50
(d) exotic birds	25

(a)	not more than three bedrooms within the dwelling unit are used to provide such sleeping accommodation;
(b)	the dwelling unit is the principal residence of the persons receiving the remuneration and providing the sleeping accommodation and one meal per day; and,
	members of the general public, for periods of one week or less, and in which:
	unit for the purpose of providing, for remuneration, sleeping accommodation and one meal per day to
	Bed and Breakfast Home: a dwelling unit in which the occupants thereof use a portion of the dwelling
	Bare Land Unit: a bare land unit as defined in <i>The Condominium Property Act, 1993.</i>
	Bare Land and Condominium: a condominium divided into bare land units, as defined in <i>The Condominium Property Act, 1993.</i>
	Applicant: a developer or person applying for a development permit under this bylaw.
	Auction Market: a building, structure, or lot, or part thereof, used as a premises where goods and materials that are to be sold by public auction.
(7) <u>Horses</u>	
(a) domesticated native ungulates	1
(b) other than colts or ponies	1
(c) colts or ponies	2
(d) calves	4
(e) replacement heifers	2
(f) foeder cattle	1.5
(g) cows or bulls	1
(6) <u>Cattle</u>	
(a) rams or ewes	7
(b) lambs	14
(c) weanling pigs	20
(d) feeder pigs	6
(e) gilts	4
(f) boars or sows	3
(3) <u>Wild Boars</u>	
(a) boars or sows	3
(b) gilts	4
(c) feeder pigs	6
(d) weanling pigs	20
(2) <u>Hogs</u>	
(a) boars or sows	3
(b) gilts	4
(c) feeder pigs	6
(d) weanling pigs	20
(4) <u>Sheep</u>	
(a) rams or ewes	7
(b) lambs	14
(5) <u>Goats, Llamas, Alpacas, etc.</u>	7
(6) <u>Cat</u>	1
(7) <u>Dog</u>	1
(8) <u>Other</u>	
(a) deer, elk, bison, etc.	1

- (c) the meal which is provided is served before noon each day.

Bin Yard: a site used for the storage of grain, fertilizer, machinery and other equipment by bins, storage buildings and other structures intended to accommodate the site.

Bin Yard, Commercial Related: a bin yard that supports an agricultural related commercial or industrial use (see Use, Agricultural Related Commercial or Industrial).

Bin Yard, Farm Related: a bin yard that supports a farm operation (see Farm Operation).

Building: a structure used for the shelter or accommodation of persons, animals, or chattels.

Building Bylaw: any bylaw of the Rural Municipality of Mountain View No. 318 regulating the erection, alteration, repair, occupancy or maintenance of buildings or structures.

Building Development: means the primary building that is currently occupied, or capable of immediate occupation, for human habitation and that meets the definition of one of the following:

- (a) bed and breakfast;
- (b) residential care facility;
- (c) custodial care facility;
- (d) business dwelling;
- (e) dwelling; or
- (f) farm dwelling.

Building Floor Area: the maximum habitable area contained within the outside walls of a building, excluding in the case of a dwelling unit any private garage, porch, sunroom, unfinished attic or unfinished basement.

Building Height: the vertical distance of a building measured from grade level, 0.3 metres back from the principal building to the highest point of the roof surface.

Building Line, Established: a line, parallel to the front site line (and, in the case of corner sites, a line, parallel to the side site line along the flanking street), and set back the average distance from the edge of the street to the main walls of the existing buildings on a side of any block of the street where more than half the lots have been built on.

Building Permit: a permit issued under a building bylaw of the municipality authorizing the construction of all or part of any building.

Building, Principal: the main building in which the principal use of the site is conducted.

Business Dwelling: an accessory dwelling unit accessory to a commercial or industrial use in a commercial, industrial or agricultural zoning district that is intended to accommodate an owner, manager, employee of the company who must live onsite to accomplish their tasks.

Campground: the seasonal operation of an area of land managed as a unit, providing temporary short-term accommodation for tents, tent trailers, travel trailers, recreational vehicles and campers, used by travelers and tourists.

Campsites: a designated and delineated area within a campground or tourist camp that is intended to

		Deck: a raised open platform, with or without rails, attached to a principal building.
		Day Care Centre: a facility for the non-parental care of over four (4) preschool age children on a daily basis and licensed under <i>The Child Care Act</i> .
		in which the number of persons in detention, custody or residence does not exceed five.
	(b)	program pursuant to <i>The Correctional Services Act</i> .
(a)		a facility for the accommodation of persons participating in a community training program pursuant to <i>The Youth Criminal Justice Act</i> (Canada) or <i>The Summary Offences Procedure Act</i> , 1990 (Saskatchewan); or,
		provisions of <i>The Rural Municipality of Mountain View No. 318 Zoning Bylaw</i> which is owned by a municipality of less than 60% of the total perimeter enclosed by walls, doors or windows and is attached to a principal building.
		Cemetery: property used for the interment of the dead and may include facilities for the storage of ashes of human remains that have been cremated.
		Car Wash: a building or portion of a building which is used for the washing of vehicles, including full service, automatic and hand operated facilities.
		Carpark: a roofed enclosure for the parking of a motor vehicle or vehicles which has less than 60% of the total perimeter enclosed by walls, doors or windows and is attached to a principal building.
		Cannabis Retail Store: a retail store, approved under federal and provincial regulations that sells cannabis and any of its derivatives.
		Cannabis Production Facility: a facility, approved under federal and provincial regulations, that is used in whole or in part for the planting, cultivation, testing, harvesting, processing and distribution of the cannabis plant and any of its derivatives.
		accommodate a single tenant, tenet party or recreational vehicle.
		Construction Trades: offices, shops and warehouses, with or without associated retail sales of plumbing and heating, electrical, carpentry, masonry and other trades associated with construction of buildings, and which is owned by a municipal corporation, non-profit organization or other non-profit organization.
		Convenience Store: a store offering for sale primarily food products, beverages, tobacco, personal care items, hardware and printed matter and which primarily provides a convenient day-to-day service to residents in the vicinity.
		Council: the Council of the Rural Municipality of Mountain View No. 318.
		Cultural Institution: an establishment such as a museum, art gallery, library and similar facilities of historical, educational or cultural interest.
		Custodial Care Facility: either:
		Community Centre: a building or facility used for recreational, social, educational or cultural activities and which is owned by a municipal corporation, non-profit organization or other non-profit organization.
		Construction Trades: offices, shops and warehouses, with or without associated retail sales of plumbing and heating, electrical, carpentry, masonry and other trades associated with construction of buildings, and which is owned by a municipal corporation, non-profit organization or other non-profit organization.
		Convenience Store: a store offering for sale primarily food products, beverages, tobacco, personal care items, hardware and printed matter and which primarily provides a convenient day-to-day service to residents in the vicinity.
		Council: the Council of the Rural Municipality of Mountain View No. 318.
		Cultural Institution: an establishment such as a museum, art gallery, library and similar facilities of historical, educational or cultural interest.
		Custodial Care Facility: either:
		Day Care Centre: a facility for the non-parental care of over four (4) preschool age children on a daily basis and licensed under <i>The Child Care Act</i> .
		Deck: a raised open platform, with or without rails, attached to a principal building.

Development: the carrying out of any building, engineering, mining or other operations, in, on, or over land, or the making of any material change in the use or intensity of use of any building or land.

Development Permit: a document authorizing a development issued pursuant to this Bylaw.

Dwelling: a building used or intended for residential occupancy and may include a Modular Dwelling or a Ready-to-Move Dwelling, but excluding a Manufactured Dwelling or Mobile Home Dwelling, as herein defined.

Dwelling, Garden Suite: a self-contained dwelling unit that is located in the rear yard or side yard of a site in which the principal use is a single detached dwelling, and to which the suite is an accessory use.

Dwelling Group: a group of two or more detached one unit dwellings, two unit dwellings or multiple unit dwellings or combinations thereof occupying the same site.

Dwelling, Modular: a dwelling which is constructed of pre-fabricated parts, unit modules and/or finished sections built in a factory, conforming to CSA Standard A277, and which are transported to this site for assembly on an approved foundation which complies with the requirements of the National Building Code.

Dwelling, Manufactured: a dwelling that conforms to the CSA Standard Z240.2.1 and amendments thereto.

Dwelling, Multiple Unit: a building divided into three or more dwelling units as herein defined and shall include townhouses and apartments but not hotels, or motels.

Dwelling, Multiple Unit Apartment Style: a building divided into three or more units as herein defined, each of which is occupied or intended to be occupied as a permanent home or residence and is accessed from the outside, a common indoor area, or both, but not including hotels, motels or townhouses.

Dwelling, Multiple Unit Townhouse: a multiple unit dwelling in which each unit has its own entrance to the outside and each unit is separated from other units by a common wall or ceiling which has no openings.

Dwelling, Secondary Suite: a self-contained dwelling unit that is an accessory use to, and located within, a building in which the principal use is a single detached dwelling.

Dwelling, Ready-to-Move (RTM): a ready-to-move one unit dwelling which is built to completion off-site using conventional lumber and building practices according to the current National Building Code of Canada, and which is transported to the site as a complete unit for placement on a fixed approved foundation which complies with the requirements of the National Building Code of Canada.

Dwelling, Semi-Detached: a dwelling unit on its own site, with a common wall dividing the two dwelling units through at least 30% of the depth of the entire structure, measure from the front to the rear building lines.

Dwelling, Single Detached: a detached building consisting of one dwelling unit as herein defined, but shall not include a manufactured home as herein defined.

Dwelling, Street Townhouse: a dwelling unit, designed as one cohesive building in terms of architectural

Fish Management Activities: activities involved in the proper management of an area of a water body

Financial Institution: a bank, credit union, trust company, or similar establishment.

Fence: an artificially constructed barrier erected to enclose or screen areas of land.

- (o) other product which incorporate the use of food, feed, fibre or fur
- (n) equine and other similar products; and,
- (m) apiaries and honey production;
- (l) trees;
- (k) grasses;
- (j) seeds;
- (i) flowers;
- (h) vegetables;
- (g) fish;
- (f) fruits;
- (e) livestock, including breeding and grazing;
- (d) poultry and poultry products;
- (c) dairy and dairy products;
- (b) grains and feed crops;
- (a) forages and sod crops;

Farm Product: those plants and animals useful to man and including, but not limited to:

Inensive Agricultural Operations.

Farm Operation: conditions or activities which occur on a farm in connection with the commercial production of farm products, including agriculture, but not including intensive Livestock Operations or

Farm Based Business: an occupation carried on by the operators of a farm, ancillary to the principal use.

Farm Dwelling: an accessory dwelling on a farm that is intended to accommodate farm workers.

Farm: the land, buildings, and machinery used in the commercial production of farm products.

1:100 peak calm level with a 1:5 wind from the most critical direction for most lakes.

area. It is based on the 1:500 peak flow for rivers, and the higher of the 1:500 peak calm level or the 1:100 peak calm level with a 1:5 wind from the most critical direction for most lakes.

Dwelted Peak Water Level (E.P.W.L.): the calculated water level used to determine the flood hazard a private school.

Educational Institution: post-secondary college, university or technical institution, but shall not include microwave ovens or other cooking appliances.

“kitchen components” include, but are not limited to, cabinents, refrigerators, sinks, stoves, ovens, facilities, sanitary facilities and a kitchen or kitchen components. For the purpose of this definition, facilities, sanitary facilities and a kitchen or kitchen components.

Dwelling Unit: a separate set of living quarters, whether occupied or not, usually containing sleeping including single detached dwellings which contain a secondary suite as defined herein.

Dwelling, Two-Unit: a building divided into two separate dwelling units on the same site but not including single detached dwellings which contain a secondary suite as defined herein.

has direct access to the outside at grade and is not wholly above another dwelling.

and the surrounding shoreline for the continuous production of fish therefrom.

Flankage: the side site line of a corner site which abuts the street.

Flood Hazard Area: the flood hazard area the area below the E.P.W.L. The flood hazard area has two zones; the Flood Fringe and the Floodway.

Flood Fringe: a zone within the flood hazard area where some types of development may occur if suitably flood-proofed. The Flood Fringe is typically defined as that portion of the flood hazard area where:

- (a) depth of inundation above natural ground is less than 1.0 metre;
- (b) flow velocities are less than 1.0 metre per second; and,
- (c) encroachment (fill) into the Flood Fringe would raise upstream water levels by less than 0.3 metres.

Floodway: a zone within the flood hazard area where typically only necessary infrastructure is allowed (eg. water intakes and outfalls, bridge piers and abutments, etc.) or development that is of low value and non-obstructive (eg. parks, nature areas, parking lots, and recreational trails). The Floodway contains the deepest, fastest, and most destructive floodwaters and is typically defined as that portion of the flood hazard area where:

- (a) depth of inundation above natural ground is more than 1.0 metre;
- (b) flow velocities are greater than 1.0 metres per second; or,
- (c) encroachment (fill) into the Floodway would raise upstream water levels by more than 0.3 metres.

Flood Proofing: techniques or measures taken to permanently protect a structure or development from flood damage. These can include measures such as elevating building (eg. building on fill or piers), constructing dykes, creating upstream storage, diversions, and channelization.

Foreshore: the Crown Land lying between the shore of any watercourse and registered surface parcels.

Gas Bar: a building or facility used for the retail sale of motor vehicle fuels from fixed pumps.

Hazard Land: land which may be subject to flooding, ponding, slumping, subsidence, landslides, erosion, or contamination by hazardous material.

Hazardous Material: any product, substance or organism which, because of its quantity, concentration or risk of spill, or its physical, chemical or infectious characteristics, either individually or in combination with other substances, is an existing or potential threat to the physical environment, to human health or to living organisms, including but not limited to:

- (a) corrosives;
- (b) explosives;
- (c) flammable and combustible liquids;
- (d) flammable solids. substances liable to spontaneous combustion, substances that on contact with water emit flammable gases;
- (e) gases, compressed, deeply refrigerated, liquified or dissolved under pressure;
- (f) oxidizing substances; organic peroxides;
- (g) poisonous (toxic) and infectious substances;

- Health Care Clinic:** a facility or institution engaged in the provision of services for health maintenance, diagnosis or treatment of human pain, injury or other physical condition on an out-patient basis.
- (h) radioactive materials;
- (i) waste Dangerous Materials; and,
- (j) any other environmentally hazardous substance.
- Highway Sign Corridor:** a strip of land parallel and adjacent to a provincial highway where private signs may be permitted to advertise goods and services of local area businesses and attractions, as provided by regulations of the Department of Highways and Transportation entitled "The Erection of Signs Adjacent to Provincial Highway Regulations, 1986", as may be amended from time to time and as managed by the Village of Marsden.
- Home Based Business:** an occupation carried on by the occupants of a residence ancillary to a principal use.
- Hotel:** a building or part of a building used as a place for sleeping accommodation with or without meals, and which may have a licensed beverage room, but does not include a motel.
- Institutional Camp:** an area of land containing sleeping accommodations and facilities which are used to provide short term accommodation for persons engaged in passive recreation or leisure, which, without limiting the generality of the foregoing, shall include the following: children's camp or establishment, religious camp, artist's camp, retreat, educational camp, recreation camp, sports camp or other similar camp or establishment.
- Intensive Agricultural Operation (ILO):** the operation or facilities for rearing, confinement or feeding of poultry, hogs, sheep, goats, cattle horses or domesticated game animals, in such numbers that the facility but not including an intensive livestock operation.
- Intensive Livestock Operation:** a principal use that produces a crop that is grown in buildings or under structures, using hydroponic techniques, or by use of intensive integration and fertilizer application.
- Intersection:** an area where two or more streets or lanes meet or cross at grade.
- (a) will contain 300 or more animal units; and,
- (b) provides less than 370 m^2 of space for each animal unit contained therein.
- Junk and Salvage Yards:** uses including, but not limited to, uses involved in salvaging, storing or selling scrap metal, paper, plastic, glass, wood and other waste material, as well as unlicensed vehicles and used vehicles parts.
- Kennel:** the temporary accommodation of dogs, cats or other domestic animals for commercial purposes.
- Lakeshore:** the line denoting the ordinary high water mark for any lake.
- Landscaping:** the modification and enhancement of a site through the use of any or all of the following elements:
- (a) hard landscaping: landscaping consisting of non-vegetative materials, such as brick, stone, concrete, tile and wood, but excluding monolithic concrete and asphalt;
- Rural Municipality of Mountain View No. 318 Zoning Bylaw**

- (b) *soft landscaping*: landscaping consisting of vegetation, such as trees, shrubs, hedges and grass;
- (c) *architectural elements*: landscaping consisting of wing walls, sculptures, etc.

Landscaping establishment: establishments primarily engaged in providing landscape care and maintenance services including the sale and / or installation of trees, shrubs, plants, lawns or gardens, and establishments engaged in these activities along with the construction (installation) of walkways, retaining walls, decks, fences, ponds and other similar structures and the retail sale of soft landscaping materials such as plants, trees, shrubs, as well as hard landscaping materials such as bricks, pavers, shale, crushed rock or other similar materials associated with landscaping, but does not include on-site outdoor and indoor cultivation or propagation of plants (green housing).

Lane: a public highway vested in the Crown as a secondary level of access to a lot or parcel of land.

Linear Park: dedicated land developed in a linear fashion, between 15 and 35 metres in width, intended to facilitate pedestrian and cycling transportation, and may also facilitate the management of storm water.

Loading Space: a space, measuring at least 2.4 metres in width and 8.4 metres in depth, located on a site, and having access to a street or lane, in which a vehicle may park to load or unload goods.

Lot: an area of land with fixed boundaries and which is of record with the Information Services Corporation by Certificate of Title.

Lounge: a room or area adjoining a restaurant that permits the sale of beer, wine or spirits for consumption on the premises, with or without food, and where no entertainment or dance floor is permitted, either in the lounge or in the restaurant attached to the lounge.

Mall: a single story commercial building in which, up to six (6) commercial uses are located together for their mutual benefit, each use having a separate entrance to the outside.

Manufactured Home Court: any parcel of land on which two or more occupied manufactured homes are located and includes any structure used or intended to be used as part of the equipment of such manufactured home court.

Manufactured Home Site: an area of land in a manufactured home court for the placement of a manufactured home.

Manufactured Home Subdivision: any residential subdivision of land containing lots under either freehold or leasehold tenure for the purpose of accommodating manufactured homes in such a manner that each manufactured home is situated on its own lot and in which all such lots, public open spaces, internal streets and lanes, buffer zones and other amenity areas form a contiguous area of development.

Manufacturing and Processing Facilities: the manufacturing and assembly of goods, products or equipment and / or the processing of raw or finished materials, including the servicing, repairing or testing of materials, goods, equipment normally associated with the manufacturing, processing or assembly operation. It may include any indoor display, office, technical or administrative support areas or any sales operation accessory to the principal use.

Manufacturing and Processing Facilities, Light: manufacturing and processing facilities where all operations are contained within an enclosed building.

Non-Conforming Site: a site, consisting of one or more contiguous parcels, that on the day of a zoning bylaw or any amendment to a zoning bylaw becomes effective, contains a use that conforms to the zoning bylaw but the site area or site dimensions do not conform to the standards of the zoning bylaw for that use.

- (a) that is lawfully constructed or lawfully under construction, or in respect of which all required permits have been issued, at the date Zoning Bylaw or any amendment to this Bylaw affecting the building or land on which the building is situated or will be situated becomes effective; and,
- (b) that on the date this Bylaw or any amendment to this Bylaw becomes effective does not, or when constructed will not, comply with this Bylaw.

Non-Conforming Building: a building:

Nacelle: the framing and housing at the top of a wind tower that enclose the gearbox and generator.

Municipality: The Rural Municipality of Mountain View No. 318.

- (a) office and meeting space;
- (b) storage of municipal equipment and supplies;
- (c) recreation; and/or,
- (d) other institutional purposes.

Municipal Facility: land and / or structures owned by the Municipality that are used for:

Motor Vehicle, Farm and Heavy Equipment Use: any building, premises or land in which or upon which a business, service or industry involving the maintenance, servicing, storage or repair of commercial vehicles is conducted or rendered, including the dispensing of motor fuel or other petroleum products directly into motor vehicles and the sales of accessories or equipment for trucks or similar commercial vehicles.

Motel: an establishment consisting of a group of attached or detached living or sleeping accommodations each with a bathroom, located on a lot or site and designed for use by the public, and may include a restaurant or licensed dining room.

Minister: the member of the Executive Council to whom, for the time being, is assigned the administration of The Planning and Development Act, 2007.

Mineral Resource Processing: the blasting, crushing, washing, screening, weighing, sorting, blending and/or refining of mineral resources.

Membrane-Covered Structure: a structure consisting of a frame that is covered with plastic, fabric, canvas or similar non-permanent material, which typically is used to provide storage for vehicles, boats, materials. The terms shall also apply to structures known commonly as hoop houses, canopy-covered carports, and tent garages, and can be fully or partially covered. Gazebos are not membrane-covered structures.

Marina: a building, structure or place, containing docking facilities and located on a waterway, where boats and boat accessories are stored, serviced, repaired or kept for sale and where facilities for the sale of marine fuels and lubricants may be provided.

Non-Conforming Use: a lawful specific use:

- (a) being made of land or a building or intended to be made of land or a building lawfully under construction, or in respect to which all required permits have been issued, on the date of this bylaw or any amendment hereto becomes effective; and,
- (b) that on the date this Bylaw or any amendment hereto becomes effective does not, or in the case of a building under construction or in respect of which all required permits have been issued, will not comply with this Bylaw.

Office and Office Building: a building or part of a building used primarily for conducting the affairs of a business, profession, service, industry or government in which no goods or commodities of business trade are stored, transhipped, sold or processed.

Official Community Plan (OCP): The Rosetown Hub and Spoke District Official Community Plan Bylaw, as most recently amended, for the Rural Municipality of Mountain View No. 318.

Outfitter Base Camp: a commercial recreation facility that provides outfitting services by a licensed outfitter and which may include accommodation licensed under *The Public Accommodation Regulations* and the storage and provision of related outfitting equipment, or the dressing, butchering, cleaning or freezing of game or fish, as part of the service.

Outfitting Equipment: equipment and supplies, including boats, canoes and other water vessels, aircraft, motor vehicles, motors, fuel, fishing and hunting gear and any other equipment for use in:

- (a) hunting, taking or catching wildlife;
- (b) angling, taking or catching fish; and/or,
- (c) ecotourism, including the viewing and photographing of natural areas, flora and fauna.

Parking Lot: an open area of land, other than a street, used for the temporary parking of more than four vehicles and available for public use whether cost-free, for a fee or for accommodation of clients or customers.

Parking, Off-Street: accommodation for the parking of vehicles off a public street or lane.

Parking Space, Vehicle: a space within a building or parking lot for the parking of one vehicle, having minimum dimensions of 2.4 metres wide by 5.5 metres deep, and which has access to a developed street or lane.

Passive Recreation Use: a recreational land use that does not require significant development upon the site and does not lessen the natural character of the area.

Personal Service Shops: establishments engaged in providing the care of a person or their apparel, which include barber shops, hairstyle salons, laundries, dry cleaners, shoe repair, photographic studios and other similar uses.

Photography Studio: a place used for portrait or commercial photography, including the developing and processing of film, and the repair or maintenance of photographic equipment.

Place of Worship: a place used for worship and related religious, philanthropic or social activities and includes accessory rectories, manses, meeting rooms and other buildings. Typical uses include churches, chapels, mosques, temples, synagogues and parish halls.

Repair Shops and Repair Services, Enclosed: repair shops and repair services where all operations are

motors.

Repair Shops and Repair Services: a place where personal effects and household goods and appliances are repaired including the repair of large equipment such as motor vehicles, heavy equipment or heavy

addition of new floor space to an existing single detached dwelling.

development or conversion of base ment space or above-grade space to a separate dwelling unit, or the development of new floor space to an existing single detached dwelling.

Rental Suite: dwelling unit located within, and accessory to, a single detached dwelling, including the

Reeve: the Reeve of the Rural Municipality of Mountain View No. 318.

(c) outdoor compaction.

(b) collection and storage of paints, oil, solvents or other hazardous material; nor,

(a) processing of recyclable material other than compaction;

be allowed at a recycling collection depot.

Recycling Collection Depot: a building or structure used for collection and temporary storage of recyclable household material such as bottles, cans, plastic containers and paper. The following shall not

Recreational Vehicle, Park Model: a recreational vehicle that conforms to Canadian Standards Association, Construction Standard No. Z241 Series, Park Model Trailers.

Recreation Vehicle: a unit intended to provide temporary living accommodation for campers or travellers; built as part of, or to be towed by, a motor vehicle, and includes truck campers, motor homes, tent trailers, fifth wheels, travel trailers and park model trailers.

Recreational Facility: a recreation or amusement facility open to the general public.

Public Utility: a government, municipality or corporation under Federal or Provincial statute which operates a public work.

- (f) facilities for the collection, storage, movement and disposal of storm drainage.
- (e) telephone, internet, cable television or light distribution or transmission lines; and,
- (d) facilities for the collection, treatment, movement or disposal of sanitary sewage;
- (c) facilities for the storage, transmission, treatment, distribution or supply of water;
- (b) systems for the distribution, storage or transmission of natural gas or oil;
- (a) systems for the production, distribution or transmission of electricity;

Public Work: means:

Public Utility: a government, municipality or corporation under Federal or Provincial statute which operates a public work.

Public Hospital: a hospital operated by the Regional Health Authority.

Principal Building: the main building in which the principal use of the site is conducted.

Preschool: a facility which provides a program for preschool aged children.

contained within an enclosed building.

Residential Care Facility: a facility licensed under provincial statute to provide, in a residential setting, long term residential, social, physical, or personal care, including accommodation, meals, supervision or assistance for persons who have limits on ability for self-care, self supervision, and who are unrelated to the operator or owner.

Restaurant: a place where food and beverages are prepared and served to patrons seated at tables or counters, in a motor vehicle on the premises, or for off-site consumption, and may include a drive-through service window.

Retail / Service Commercial: the sale or display of merchandise to the public, including the storage of merchandise on or about the premises in quantities sufficient only to supply the establishment or establishments engaged in such merchandise sales, or providing the care of a person or their apparel and accessories, including but not limited to childcare services, beauty salons and barber shops, massage services, health clubs, tanning beds, spas, esthetician services, laundry services, laundromats, dry cleaning, shoe repair, tailor or seamstress services, photographic studios and other similar uses, including the provision of health related services.

Rotor: the blades and hubs of a wind turbine that rotate during its operation.

Rural Municipal Administrator: the Rural Municipal Administrator(s) for the Rural Municipality of Mountain View No. 318.

Safe Building Elevation (S.B.E.): the level defined by The Ministry of Municipal Affairs at time of subdivision and by municipal bylaw to which flood-proofing must be undertaken for developments in the flood hazard area. The S.B.E. is calculated as the E.P.W.L. plus a freeboard value. The freeboard allows for uncertainties in the calculations, and for other possible hazards such as ice shove, ice jams, and erosion. The Saskatchewan Watershed Authority usually recommends a freeboard of 0.5 m for most situations. For dykes used as flood-proofing, a freeboard of 0.6 m is usually recommended. In areas with high uncertainty in the hydrology or hydraulic response of the lake or river, a freeboard of up to 1.0 m may be recommended.

School: a body of pupils that is organized as a unit for educational purposes, that comprises one or more instructional groups or classes, together with the principal and teaching staff and other employees assigned to such body of pupils, and includes the land, buildings or other premises and permanent improvements used by and in connection with that body of pupils.

Screening: a fence, wall, berm or planted vegetation located so as to visually shield or obscure one abutting area of use from another.

Service Station: a place where petroleum products are kept for retail sales for automobiles and other motor vehicles and where repairs, rental, servicing, greasing, adjusting or equipping of automobiles or other motor vehicles may be performed, but not including painting, body work and major repairs.

Sight Triangle: the triangular area formed, on corner sites, by the intersecting front and side site lines at a street intersection and the straight line joining said site lines.(refer to Figure 2-2).

LAND USE

Site, Through: a site not more than one lot in depth, having a frontage on two streets more or less parallel (refer to Figure 2-3).

Site, Lakeshore: any residential site that abuts the bank of the lake, or abuts the foreshore.

Site, Interior: a site other than a corner site (refer to Figure 2-3).

Site, Corner: a site at the intersection or junction of two (2) or more streets (refer to Figure 2-3).

Site: one or more contiguous lots under one ownership and used, or intended to be used, by a single principal use.

- (a) is a structure or any part thereof, or is attached to, painted on, or in any manner represented on a building;
- (b) is used to announce, direct attention to, or advertise a use or building; or,
- (c) is visible from outside the building

Sight: any writing (including letter or word), billboard, pictorial representation (including illustration or decoration), emblem (including device, symbol or trademark), flag (including banner or pennant), or any other figure of similar character which:






Figure 2-3: Illustration of Site Definition

Site Coverage: that portion of the site that is covered by principal and accessory buildings.

Site Drainage Plan: a plan which shows the existing and proposed topography of a site, with contour intervals and drawn to scale, with appropriate dimensions and sufficient spot elevations to adequately demonstrate to the Development Officer that the proposed drainage pattern will not have an adverse effect on neighbouring properties and streets.

Site Frontage:

- (a) for Rectangular Sites: the horizontal distance between the side site lines of the site measured along the front site line.
- (b) for Non-Rectangular Sites: the average of the horizontal distances between the side site lines of the site measured along the front and rear site lines.

Site Line, Front: the boundary at the front of the site.

Site Line, Rear: the boundary at the rear of the site and opposite the front site line.

Site Line, Side: a site boundary other than a front or rear site line.

Solar Farm: Systems designed for the primary purpose of generating power for the sale to third parties

Trailer Coach: any vehicle used or constructed in such a way as to enable it to be used as a convenience upon public roads or highways and includes a self-propelled or non-self-propelled vehicle designed,

Training Centre: an establishment that conducts technical training and instruction in a technical subject or trade.

Tourist Camp: a facility which has two or more cabins for the accommodation of the travelling public and may also have provision for the accommodation of trailers, tent trailers, tents and recreational vehicles.

Tourism Base Camp: a commercial recreation facility which provides outfitting services for the viewing of natural areas and wildlife, but not including services for hunting, trapping, catching or angling of wildlife or fish, and which may include accommodation licensed under *The Public Accommodation Regulations* and the storage and provision of related outfitting equipment.

Temporary Work Camp: a temporary residential complex used to house camp workers by various contractors made up of a number of mobile units, clustered in such fashion as to provide sleeping, eating, recreation and other basic living facilities.

Temporary Use: a use established for a fixed period of time and that is to be discontinued upon the expiration of the time period specified for that use.

Temporary Building: a building without a foundation or footing, and that is to be removed upon the expiration of a designated time period.

- (e) any other tower or structure used for receiving and/or transmitting electromagnetic radiation;
- (d) radio and television towers and associated facilities; and,
- (c) radar stations;
- (b) internet receiving and/or transmittal towers and associated facilities;
- (a) microwave towers, including mobile (cellular) phone towers and associated facilities;

Telecommunications Facility: includes,

Supply Depot: a facility that specializes in the bulk storage and sale of products and supplies.

Subdivision: a division of land as described in the regulations pursuant to *The Land Survey Act*, 2000.

Structure: anything that is built, constructed, or erected, located in, on, or over the ground, or attached to something located in or over the ground.

Storage Yards and Establishments: establishments primarily engaged in renting or leasing space for outdoor space) where clients retrieve and store their goods.

Street: a public road or thoroughfare registered by plan of survey which affords the principal of access to abutting property, but shall not include an easement or lane.

Via the electric grid. The systems can be roof-mounted systems or ground-mounted systems that may or may not have accessory structures on the same site.

constructed or reconstructed in such a manner as to permit occupancy as a dwelling or sleeping place for one or more persons notwithstanding that its running gear is removed or that it is jacked-up

Transloading Facility for Oil and Gas Resources: means a facility used to transfer oil and gas resources from one mode of transportation to another and may include rail lines, pipelines, tank storage, rail loading buildings, instrumentation, related office buildings, and other related facilities.

Trapping: the taking of fur animals by a trapper licensed under *The Wildlife Act, 1998* and associated regulations, by means of traps, where the trapper has several traps operating at one time and checks them in a planned and regular manner, and may include temporary accessory buildings secondary and accessory to the use.

Tree Nursery: the use of land for raising shrubs, trees and bedding plants.

Truck Stop: any building, premises, or land in which or upon which a business, service, or industry involving the maintenance, servicing, storage, or repair of commercial vehicles is conducted or rendered, including the dispensing of motor fuel or other petroleum products directly into motor vehicles and the sales of accessories or equipment for trucks or similar commercial vehicles. A truck stop shall also be defined to include those overnight accommodations and restaurant facilities primarily for the use of truck crews.

Use: the purpose or activity for which a piece of land or its buildings is designed, arranged, occupied or maintained.

Use, Agricultural Related Commercial or Industrial: a service to the agricultural community such as grain and seed cleaning and drying, fertilizer distribution, implement and machinery assemblage, sale and service, veterinary clinics, hatcheries, apiaries, bulk fuel sales, stock yards, feed mills, oil seed processing plants, and other similar uses.

Use, Discretionary: a use or form of development that may be allowed in a zoning district following application to, and approval of the Council; and which complies with the development standards, as required by Council, contained in this Bylaw.

Use, General Industrial: shall mean any of the following activities:

- (a) the processing of raw or finished materials;
- (b) the manufacturing or assembly of goods and equipment;
- (c) the cleaning, servicing, repairing or testing of materials, goods and equipment normally associated with industrial or commercial businesses or cleaning, servicing and repair operations to goods and equipment associated with personal or household use, where such operations have impacts that would make them incompatible with non-industrial development;
- (d) the storage or transhipping of materials, goods and equipment, including warehouses;
- (e) the training of personnel in general industrial operations; and/or,
- (f) indoor display, office, technical or administrative support areas or any sales operation accessory to the general industrial use.

Use, Hazardous Industrial: an industrial use involving the manufacturing, storage, processing, transhipment, collection, treatment or disposal of hazardous materials or chemicals (specifically excluding agriculture fertilizer, herbicide or pesticide warehousing and/or sales facilities, depots for the collection of farm chemical containers, ethanol and biodiesel plants and associated production facilities,

Yard, Front: that part of a site which extends across the full width of a site between the front site line and

Yard: an unoccupied space open to the sky on the same site with a building or structure.

Wind Turbine: a device that converts kinetic energy of the wind into rotational energy to turn an electrical generator shaft. A wind turbine typically consists of a rotor, nacelle and supporting tower. The height of a wind turbine is measured from the base of the tower foundation to the highest point of the blades at their apex.

Wind Farm: a wind energy facility consisting of two or more wind turbines.

Wind Energy Facility: a single wind turbine and all equipment, machinery and structures utilized in connection with the conversion of wind to electrical energy. This includes, but is not limited to, all associated transmission, storage, collection and supply equipment, substations, transformers, site access, service roads and machinery.

Wildlife Management Activities: activities involved in the proper management of an area or region for the continuous production of wildlife theretofore.

Waste Management or Disposal Facility, Solid: a facility, not including a waste transfer station, to accommodate discarded materials, substances or objects which originated from residential, commercial, institutional and industrial sources which are typically disposed of in municipal or private landfills, but not including dangerous goods, hazardous waste or biomedical waste.

Waste Management or Disposal Facility, Liquid: a facility to accommodate any waste which contains animal, mineral or vegetable matter in solution or suspension, but does not include a manure storage area for an intensive livestock operation.

Wholesale Establishment: the sale of commodities to retailers or jobbers and shall include the sale of commodities for the purpose of carrying on any trade or business.

Warehouse: a building used primarily for the storage of goods and materials.

Veterinary Clinic: a place for the care and treatment of small and/or large animals involving outpatient care and medical procedures involving hospitalization, and may include the keeping of animals in outdoor pens.

Use, Prohibited: any use or form of development that is not allowed because it is not listed as permitted or discretionary. Use within a given zoning district, or because it is specifically prohibited elsewhere in this Bylaw.

Use, Principal: the main purpose for which a building, structure, or site is used.

Use, Permitted: any use or form of development, other than a discretionary use, specifically allowed in a zoning district subject to the regulations applicable to that zoning district.

Use, Petroleum Related Commercial: a service to the petroleum and natural gas extraction industry such as drilling and oil well servicing operations, hauling services and storage facilities and other similar uses.

and transloading facilities for oil and gas resources).

the nearest main wall of a building or structure.

Yard, Rear: that part of a site which extends across the full width of a site between the rear site line and the nearest main wall of a building or structure.

Yard, Required: the minimum yard required by this Bylaw and within which, unless specifically permitted, no building or structure, or part of a building or structure shall be erected.

Yard, Side: the part of a site which extends from a front yard to the rear yard between the side line of a site and the nearest main wall of a building or structure.

Zoning District: a specifically delineated area of the municipality within which certain uniform requirements and regulations or various combinations thereof govern the use, placement, spacing and size of land and structures.

3 ADMINISTRATION

3.1 DEVELOPMENT OFFICER

The Rural Municipal Administrator (Administrator) shall be the development officer responsible for the administration of this Bylaw. The Administrator may appoint a Development Officer subject to the approval of Council, to whom duties in the administration of the Zoning Bylaw may be delegated.

3.2 APPLICATION FOR DEVELOPMENT PERMIT

- 3.2.1 No person shall undertake a development or commence a use unless a Development Permit has first been obtained, except as provided in Section 3.3. A Development Permit cannot be issued in contravention of any of the provisions of this Bylaw subject to Sections 213 to 227 of *The Act*.
- 3.2.2 All residences require a development permit, including farm residences.
- 3.2.3 Intensive livestock and poultry operations with 300 or more animal units and providing less than 370 m² of space shall be considered intensive livestock operations, as per the definition in this Bylaw, and will also require a development permit.

3.3 DEVELOPMENTS NOT REQUIRING A DEVELOPMENT PERMIT

- 3.3.1 Development listed in Section 3.3.2 of this Bylaw must be allowed in the zoning district in which they are located and must comply with the regulations of this Bylaw.
- 3.3.2 Developments which do not require a development permit include:

(1) Accessory Farm Buildings and Structures

Farm buildings and structures, but excluding any Intensive Livestock Operation structure, where accessory to permitted agricultural use.

(2) Small Accessory Buildings

Single storey accessory buildings with a building floor area less than 9.3 m²

(3) Public Works

Any operation for the purposes of inspecting, repairing, or renewing sewers, mains, cables, pipes, wires, tracks or similar public works as required by a public utility, and the installation of service connections to property in the municipality.

Note: a permit is required for the installation of all new transmission lines and mains associated with facilities and systems for public works as defined herein.

		(3) The complete legal description of the subject property.
		(2) The proposed use of the site or building to be altered or occupied, including the area of the proposed existing building floor area to be altered or occupied, or the proposed use of the building or renovations.
		(1) The names, addresses and telephone numbers of the applicant, property owner and person or consultant who prepared the plans being submitted, including a local contact person.
3.5.1	Applications for a development permit and applications for a discretionary use, with the exception of applications for a home based business, shall be accompanied by the following:	Applications for a development permit and applications for a discretionary use, with the exception of applications for a home based business, shall be accompanied by the following:
		3.5.2 APPLICATION REQUIREMENTS
3.4.3	Where the provisions in this Bylaw conflict with those of any other municipal, provincial or federal requirement, the higher and/or more stringent standards shall prevail.	3.4.3
3.4.2	Nothing in this Bylaw shall exempt any person from complying with the requirements of a building bylaw or any other bylaw in force within the municipality, or from obtaining permission required by this or any other law or bylaw in the municipality, the province or the federal government.	3.4.2
3.4.1	A building permit shall not be issued unless a Development Permit, where required, has been issued.	3.4.1
		3.4 OTHER PERMIT REQUIREMENTS
		Subject to Section 4.12
(9)	Maintenance	Subject to the provisions of Section 4.23
(8)	Sixties	Municipality.
(7)	Temporary Confinement of Livesock	The temporary confinement of livesock during the winter months as part of a farm operation that has been issued a valid development permit.
(6)	Fences	Maintenance and repairs that do not include any structural alterations.
(5)	Maintenance	Any facility, including buildings and structures, installed and operated by the Rural Municipality.
(4)	Municipal Facilities	Rural Municipality of Mountain View No. 318 Zoning Bylaw

- (4) A copy of a site plan, drawn to scale with appropriate dimensions, showing the following information:
- (a) north arrow, roads adjacent to the site, all property boundaries, identified frontage of site, site area, site elevations, and the location of any existing buildings, structures, utility poles and wires, underground utilities, easements, building encroachments, and type and location of existing trees;
 - (b) the location and size of proposed buildings or structures, including all front, side and rear yard setback dimensions where relevant;
 - (c) the location and size of all entrances and exits to the site; and,
 - (d) the method and location of on-site sewage disposal facilities and, where proposed, manure storage facilities, including a valid sewage disposal permit issued by Public Health.

3.5.2 For certain developments or discretionary uses Council may consider proposals in the context of the information contained on the Future Land Use maps, in the Rosetown Hub and Spoke District Official Community Plan and additional information shall be required in support of the application, as follows:

- (1) Manufactured Home Court, Campground, Tourism Base Camp, Tourist Camp, Outfitter Base Camp and Institutional Camps.

An applicant for a discretionary use approval for the above-uses shall provide documentation to Council's satisfaction:

- (a) a plan of the site, identifying any buildings, uses of land and the location of all roadways, buildings, structures, manufactured home sites and campsites with dimensions. The addition or rearrangement of sites or accommodation facilities, the construction or moving of buildings, material changes in use of portions of land, or the filling or clearing of land shall require a development permit, and the applicant shall submit for approval an amended plan incorporating the proposed development.

- (2) Intensive Livestock Operation (ILO)

An application for a discretionary use approval for an intensive livestock facility shall conform to *The Agricultural Operations Act, 1996* and shall provide documentation, to Council's satisfaction, as follows:

- (a) Distances to the nearest land uses, development types and municipal limits whether within the Municipality or within an adjacent municipality, listed in "Table 7 – Required Separation Distances Between Uses" of this Zoning Bylaw and measured as specified in the notes to that table.

- (3) Intensive Agricultural Operation

An application for a discretionary use approval for an intensive agricultural operation

<p>(a) An application for a development permit for a dwelling in any country residential zoning district shall provide:</p> <p>(i) a copy of the site drainage plan, drawn to scale, with appropriate dimensions except for the following:</p> <p>(ii) development that does not involve the erection of buildings or changes in site grades.</p>
<p>(7) Dwelling in a Country Residential Zoning District</p>
<p>(a) An application for any new communal water system or communal sewer system shall include a copy of the system drawings, as required by The Public Health Act, 1994 and associated regulations, or the Environmental Management and Protection Act and associated regulations.</p>
<p>(6) New Communal Water or Sewer System:</p>
<p>(a) of distances to the nearest land uses, development types and municipal limits, whether within the municipality or within an adjacent municipality, listed in "Table 7 - Required Separation Distances Between Uses" of this Zoning Bylaw and measured as specified in the notes to that table.</p>
<p>(5) Solid or Liquid Waste Management or Disposal Facility</p>
<p>(a) of distances to the nearest permanent surface water course or permanent water body, whether within the municipality or within an adjacent municipality, listed in "Table 7 - Required Separation Distances Between Uses" of this Zoning Bylaw and measured as specified in the notes to that table; and</p>
<p>(b) of the distance to the nearest permanent surface water course or permanent water documentation, to Council's satisfaction:</p>
<p>(4) Hazardous Industrial Use</p>
<p>(a) that the water supply is sufficient for the development and that the supply for neighbouring developments will not be adversely affected by the proposed operation.</p>
<p>where intensive mitigation is required, shall provide the following documentation to Council's satisfaction:</p>

(8) Wind Energy Facility

An application for a wind energy facility shall provide documentation, to Council's satisfaction as follows:

- (a) A site location plan showing the subject property, adjacent roads, railways, telecommunications facilities (to ensure avoidance of microwave transmission corridors), property lines and all habitable buildings within one (1) one mile of the proposal.
- (b) A detailed site plan drawn to scale showing the location of the proposed wind turbine(s) and all associated facilities indicating cable locations for domestic usage and power grid connections, existing vegetation, proposed access and landscaping.
- (c) Confirmation of site ownership by the proponent or where the land is not owned by the proponent evidence of site control and right to access through provisions of a lease or easement agreement with the owner.
- (d) Proponents are responsible for obtaining any required federal or provincial permits, licenses and approvals for construction and maintenance of wind energy facilities and must remit a copy to the municipality.
- (e) Details respecting the colour and markings for the proposed tower including required lighting in accordance with federal aviation requirements.
- (f) Validation by a professional engineer of the structural integrity of the proposed supporting tower and foundation or a description of required manufacturing specifications.
- (g) For wind energy facilities consisting of two or more wind turbines additional information may be required respecting:
 - (i) illustration of sight line vistas from residential buildings within one (1) mile of the proposed development utilizing photographic representations of the development area;
 - (ii) a decommissioning plan addressing the manner of physical removal of the facility, removal of any hazardous materials and site restoration to a natural condition, should the use of the facility be discontinued.

(9) Gravel Operations

An application for excavating, stripping or grading of sand, gravel, clay or similar materials, such as gravel pits and gravel crushing operations, shall include the following documentation:

- (a) a plan showing the distances to the adjoining land uses as listed in "Table 7 - Required Separation Distances Between Uses" of this Zoning Bylaw;
- (b) a description of reclamation and rehabilitation measures to be conducted both

<p>3.6.1</p> <p>The Development Officer shall review all applications for completeness and shall inform an applicant whose application is not complete of the information or documentation required to complete the application, and that the application will not be considered until it is complete.</p>	<p>Council may impose requirements in addition to those set out above. Council may also require a performance bond by any person undertaking any work outlined in Section 3.5.2 (10) to ensure that the development is carried out in the manner specified.</p> <p>The amount of the performance bond is to be set at the discretion of Council.</p>
<p>3.6.2</p> <p>The Development Officer may submit any application to Council for a decision on the interpretation of the bylaw, or on special conditions provided in the bylaw, and shall inform the applicant of this action. Council or the Development Officer may require the applicant to provide such further information as may be required to make a decision.</p>	<p>Upon completion of a complete application for development, the Development Officer shall issue a development permit for a development that complies in all respects with the requirements of this Zoning Bylaw, the Official Community Plan and <i>The Act</i>.</p>
<p>3.6.3</p> <p>Where an application is made for a development permit with respect to a development discretionary use which has been approved by Council, the Development Officer shall issue a development permit subject to any specified development standards prescribed by Council pursuant to Section 56(3) of <i>The Act</i>.</p>	<p>Every decision of the Development Officer with respect to an application for a development permit shall be in writing and a copy of the decision shall be sent to the applicant.</p>
<p>3.6.4</p> <p>Where an application is made for a development permit with respect to a development that complies in all respects with the requirements of this Zoning Bylaw, the Development Officer shall issue a development permit for a development that complies in all respects with the requirements of <i>The Act</i>.</p>	<p>3.6.5 The Development Officer may revoke a development permit where:</p> <ul style="list-style-type: none"> (1) the development permit has been issued in error; and/or, (2) an approved development is not being developed or operated in accordance with the provisions of this Zoning Bylaw, or in accordance with the standards and conditions specified in the development permit.
<p>3.6.6</p> <p>The Development Officer shall give the reasons for denying or revoking a development permit.</p>	<p>3.6.7 The Development Officer shall give the reasons for denying or revoking a development permit.</p>

3.7 DISCRETIONARY USE APPLICATIONS

3.7.1 Discretionary Use Application Process

- (1) The following procedures shall apply to discretionary use applications:
 - (a) Applicants must file with the Development Officer a development permit application, a site plan, any other plans and information as required by the Development Officer and pay the required application and public hearing fees;
 - (b) The application will be examined by the Development Officer for conformance with the Official Community Plan, this Bylaw, and any other applicable policies and regulations;
 - (c) The Development Officer may request comments from other government agencies where applicable;
 - (d) The Development Officer will prepare a report concerning the application including recommendations that conditions be applied to an approval;
 - (e) The Development Officer will set a date for the meeting at which the application will be considered by Council and will be given notice by ordinary mail to assessed owners of property within 75 metres of the boundary of the applicant's land;
 - (f) In addition to the requirements set out in (e) above, the Development Officer shall advertise the proposed discretionary use by mailing a copy of a notice of the application to the assessed owner of each property within 1.6 kilometres of the proposed discretionary use for the following:
 - (i) any new intensive livestock operation or expansion or alteration to an intensive livestock operation;
 - (ii) kennels;
 - (iii) wind energy facilities;
 - (iv) commercial use in a residential district.
 - (g) Council shall consider the application together with the report of the Development Officer, and any written or verbal submissions received by Council;
 - (h) Council may reject the application or approve the application with or without conditions, including a condition limiting the length of time that the use may be conducted on site; and,
 - (i) The Development Officer shall notify the applicant of Council's decision by ordinary mail addressed to the applicant at the address shown on the application form.

- (3) Council's approval of a discretionary use application is valid for a period of twelve (12) months from the date of approval. An approval shall be deemed to be invalid if the proposed use or proposed form of development has not commenced within that time or if the prescribed specific time limits for a use that is intended to be temporary or to allow Council to monitor the impact of a use on surrounding development; and
- (i) intensity of use.
- (h) prescribed specific time limits for a use that is intended to be temporary or to allow Council to monitor the impact of a use on surrounding development; and
- (g) the size, shape and arrangement of buildings, and the placement and arrangement of lighting and signs;
- (f) landscaping, screening, fencing, and preservation of existing vegetation to buffer adjacent properties;
- (e) control of noise, glare, dust and odour;
- (d) appropriate space for vehicle line ups for drive through commercial facilities in order to reduce disruption of traffic flows on adjacent roadways;
- (c) adequate access and circulation for pedestrian and vehicular traffic;
- (b) the location of buildings with respect to buildings on adjacent properties;
- (a) site drainage of storm water;
- (2) Discretionary uses, discretionary forms of development, and associated accessory uses are subject to the development standards and applicable provisions of the zoning districts in which they are located. In approving any discretionary use to minimize land use conflict, Council may prescribe specific development standards related to:
- (i) advise the applicant that before the discretionary use can be considered by Council, the development shall maintain a registry of the location and all the relevant details respecting the granting of the discretionary use approval.
- (ii) advise the applicant that if the appeal is granted, the discretionary use can then be considered by Council.
- (k) Where an application for a discretionary use does not meet the zoning regulations for the applicable zoning district, the Development Officer shall:
- (l) advise the applicant that before the discretionary use can be considered by Council, the Development Officer shall issue a development permit pursuant to Section 3.7.4 of the Development Act.
- (m) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council, the development shall maintain a registry of the location and all the relevant details respecting the granting of the discretionary use approval.
- (n) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council.
- (o) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council.
- (p) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council.
- (q) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council.
- (r) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council.
- (s) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council.
- (t) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council.
- (u) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council.
- (v) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council.
- (w) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council.
- (x) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council.
- (y) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council.
- (z) advise the applicant that if the appeal is granted, the discretionary use can be considered by Council.

the Council determines, within the twelve (12) month period, that the proposed development is not proceeding in accordance with the terms and conditions of its approval. The Development Officer shall advise the applicant and Council when a prior approval is no longer valid.

- (4) Council may direct that a discretionary use permit extension be granted for an additional twelve (12) month period by the Development Officer.
- (5) If an approved discretionary use or form of development ceases to operate for a period of twelve (12) consecutive months or more, the discretionary use approval shall no longer be valid. The Development Officer shall advise the owner and Council when a prior approval is no longer valid.
- (6) Where Council has approved a discretionary use for a fixed time, as provided in this Bylaw, and that time period has expired, that use of land and/or use of buildings on that land shall cease until such time as Council gives a new discretionary use approval and a new development permit is issued.

3.7.2 General Discretionary Use Evaluation Criteria

Council will apply the following general criteria in the assessment of the suitability of an application for a discretionary use or discretionary form of development:

- (1) The proposal must be in conformance with all relevant sections of the Official Community Plan and Zoning Bylaw and must demonstrate that it will maintain the character, density and purpose of the zoning district where necessary through the provisions of buffer areas, separation and screening.
- (2) The proposal must be capable of being economically serviced by community infrastructure including roadways, water and sewer services, solid waste disposal, parks, schools, and other utilities and community facilities.
- (3) The proposal must not be detrimental to the health, safety, convenience or general welfare of persons residing or working in the vicinity or injurious to property, improvements or potential development in the vicinity.

3.7.3 Terms and Conditions for Discretionary Use Approvals

- (1) Discretionary uses, discretionary forms of development, and associated accessory uses are subject to the development standards and applicable provisions of the zoning district in which they are located. In approving a discretionary use application, Council may prescribe specific development standards to minimize land use conflict with respect to:
 - (a) site drainage of storm water;
 - (b) the location of buildings with respect to buildings on adjacent property;
 - (c) access to, number and location of parking and loading facilities including adequate vehicular access;
 - (d) control of noise, glare, dust and odour; and,

- (3) Prior to issuance of a development permit for the establishment of a gravel pit or gravel crushing operation, Council may require the developer to enter into an agreement pursuant to Section 23 of *The Act*, to define the responsibilities of the operator and responsible authorities of the developer and/or operator concerning the reclamations respecting the operation of the pit or quarry;
- (2) Council may approve discretionary use applications for a fixed period of time where it is considered important to monitor and reevaluate the proposal and its performance with the objectives of this Bylaw.
- (e) the size, shape and arrangement of buildings, and the placement and arrangement of lighting and signs to ensure compatibility with the height, scale, setbacks and design of buildings in the surrounding area, and with land uses in the general area.
- (3) Prior to issuance of a development permit for the establishment of a gravel pit or gravel crushing operation, Council may require the developer to enter into an agreement such an agreement:
- (a) Conditions respecting the operation of the pit or quarry;
 - (b) Responsibilities of the developer and/or operator concerning the reclamations of the site;
 - (c) The routing of trucks to and from the site;
 - (d) The planting of trees on and/or near the site, and/or in another location to the satisfaction of Council;
 - (e) The erection of fencing and signs;
 - (f) The maintenance of municipal roadways; and/or,
 - (g) The posting by the developer of a performance bond to guarantee adherence to the above or any other requirements that Council may specify.
- 3.7.4 Use Specific Discretionary Use Evaluation Criteria
- Council will apply the following use specific criteria to the assessment of the suitability of an application for a particular discretionary use or discretionary form of development.
- (a) The location of the bus terminal or car wash will only be favourably considered where it can be demonstrated that the use and intensity is appropriate to the site and that it will have a minimal impact on the surrounding, adjacent areas. Consideration may be given, but is not limited to the following effects:
- (i) municipal servicing capacity;
 - (ii) anticipated levels of noise, odor, smoke, fumes, dust, lighting, glare, vibration or other emissions emanating from the operation; and/or,

- (iii) anticipated increased levels or types of vehicle traffic, unsafe conditions or situations for vehicles, cyclists, or pedestrians.
- (b) Bus terminals are also subject to 4.13.9 (above ground fuel storage tanks).
- (2) *Community service uses, schools, educational facilities, clubs, places of worship, public and commercial recreation facilities:*
- (a) Schools, clubs and places of worship should, where possible, be located on corner sites to facilitate access.
 - (b) Public elementary and secondary schools should, where possible, be located adjacent to public open spaces.
 - (c) The site should be accessible from a major road network to avoid heavy traffic volumes on residential access roads.
 - (d) Consideration should be given to the location of entry and exit points of the site and their relationship with existing intersections and adjacent residential units.
 - (e) Vehicle car parking and access areas should not form a dominant element in the streetscape.
- (3) *Mineral and aggregate resource extraction industries:*
- An application for excavating, stripping or grading of sand, gravel, clay or similar materials, such as gravel pits and gravel crushing operations, shall include the following documentation:
- (a) a plan showing the location of the area of the operation relative to the site boundaries, the depth of excavation, and the quantity of material to be removed;
 - (b) a plan showing the distances to the adjoining land uses as listed in “Table 7 – Required Separation Distances Between Uses” of the Zoning Bylaw;
 - (c) a description of the excavation, stripping or grading operation proposed;
 - (d) a detailed timing and phasing program covering the time span of the proposed operation;
 - (e) a description of reclamation and rehabilitation measures to be conducted both during and following the operation consistent with The Reclamation Guidelines for Sand and Gravel Operations provided by the Ministry of Environment. These guidelines recommend that “reclamation practices should ensure a physical stabilization of the soils and achieve a sustainable land use so that the land may be returned to a productive state as soon as possible after the operation has completed” and that “reclamation operations should be carried out concurrently with extraction”;
 - (f) a description of the measures to be taken for the prevention and lessening of dust

- (g) road maintenance measures and proposed truck routes.
- and other nuisances during and after the operation; and,
- Council may impose requirements in addition to those set out above. Council may also require a performance bond by any person or company undertaking any work outlined in Section 3.7.4 (4) to ensure that the development is carried out in the manner specified. The amount of the performance bond is to be set at the discretion of Council.
- (4) Livestock auction facilities and stockyards:
- (a) The site shall be accessible from a major road network to avoid heavy traffic volumes on residential access roads.
- (b) Consideration shall be given to the location of entry and exit points of the site and their relationship with existing intersections and adjacent residential uses.
- (c) The character of adjacent residential uses shall be protected and maintained through the provision of buffer areas, separation distances and screening.
- (d) Auto body shops, construction trades and yards, transportation and trucking, freight handling facilities including railway, taxiway and accessory tanking of hides, warehouses, manufacturing and processing, welding and machine shops, metal fabricators and storage yards.
- (e) The location of the use will only be favourably considered where it can be demonstrated that the use and intensity is appropriate to the site and that it will have a minimal impact on the surrounding adjacent areas. Consideration may be given but is not limited to the following effects:
- (a) The location of the use will only be favourably considered where it can be demonstrated that the use and intensity is appropriate to the site and that it will have a minimal impact on the surrounding adjacent areas. Consideration may be given but is not limited to the following effects:
- (i) municipal servicing capacity;
- (ii) anticipated levels of noise, odour, smoke, fumes, dust, lighting, glare, vibration or other emissions emanating from the operation;
- (iii) anticipated increased levels or types of vehicle traffic, unsafe conditions or situations for vehicles, cyclists or pedestrians; and / or
- (iv) utilisation of hazardous substances.
- (b) All materials and goods used in conjunction with construction trades and manufacturing shall be stored within an enclosed building, or within an area hidden from view by screening;

- (c) Warehouses and freight handling facilities shall be accessible from a major road network to avoid heavy traffic volumes on access roads. Consideration shall be given to the location of entry and exit points to the site and their interrelation with existing intersections or land constraints; and,
 - (d) No outside storage is permitted for a wholesale establishment.
 - (e) All manufacturing and assembly operations in conjunction with a light manufacturing plant shall be conducted within an enclosed building.
- (7) *Asphalt and cement plants, gravel yards and coal yards:*
- (a) The location of the use will only be favourably considered where it can be demonstrated that the use and intensity is appropriate to the site and that it will have a minimal impact on the surrounding adjacent areas. Consideration may be given but is not limited to the following effects:
 - (i) municipal servicing capacity;
 - (ii) anticipated levels of noise, odour, smoke, fumes, dust, lighting, glare, vibration or other emissions emanating from the operation;
 - (iii) anticipated increased levels or types of vehicle traffic, unsafe conditions or situations for vehicles, cyclists or pedestrians; and / or
 - (iv) utilization of hazardous substances.
- (8) *Indoor storage rental facilities and recycling and collection depots:*
- (a) The use shall be located, where practical, in a non-highly visible area, and screened to avoid any adverse visual impact. Landscaping and screening acceptable to Council shall be provided in all yards facing a public roadway or properties in residential use.
- (9) *Campgrounds:*
- (a) Wherever possible and appropriate, any existing trees and mature landscaping shall be retained;
 - (b) Solid waste storage facilities (including adequate spaces for both recycling and general waste bins) shall be provided on-site, appropriately located, and screened or landscaped to avoid any adverse visual impact from the road and within the development.
 - (c) There shall be adequate maneuvering space on-site; and,
 - (d) The prevention of on-street congestion caused by the ingress and egress of vehicles shall be considered.

- (10) *Golf courses:*
- (a) Consideration will be given to the compatibility of the golf course with adjacent land uses;
 - (b) Insofar as possible, proposed golf courses shall respond to the natural topography and drainways of the site, and employ minimal clearing of native vegetation;
 - (c) Buffers shall be provided to protect existing, adjacent neighbourhoods by mitigating the adverse impacts of sound, visibility and traffic;
 - (d) Council will consider the following as an asset in the development of a golf course:
- (11) *Intensive agricultural uses (excluding livestock) agricultural product processing, agricultural service and contracting establishments and agricultural equipment, fuel and chemical supply establishments:*
- (i) maximum use of existing landforms and native grasses and vegetables;
 - (ii) an alternative water source to potable water; and,
 - (iii) water conserving irrigation systems.
- (12) *Truck Stops:*
- (a) An application for a truck stop shall provide documentation, to Council's satisfaction, as follows:
 - (i) The submission of an engineering report confirming an adequate portable water supply and sewage disposal system.
 - (ii) The submission of a traffic impact assessment, prepared by a professional engineer and satisfactory to the Ministry of Highways and Infrastructure, detailing level of service impacts and necessary infrastructure improvements.

(13) *Junk and salvage yards and auto wreckers:*

- (a) Junk and salvage yards and auto wreckers shall be enclosed by an opaque or solid perimeter fence at least 2.0 metres in height, and not more than five metres in height, with no material piled higher than the height of the perimeter fence; and,
- (b) The perimeter fence shall not be located in the required front yard. The required front yard shall be used for no other purpose than landscaping and necessary access driveways to the site.

(14) *Hotels and motels:*

- (a) The prevention of on-street congestion caused by the ingress and egress of vehicles shall be considered.
- (b) The site should be accessible from a major road network to avoid heavy traffic volumes on residential access roads.
- (c) Consideration should be given to the location of entry and exit points of the site and their relationship with existing intersections and adjacent residential units.

(15) *Accessory dwelling units:*

- (a) Dwelling units shall be attached to the commercial or industrial establishment and shall have a main entrance separate from that of the principal establishment. An emergency exit must be provided in addition to the main entrance; and,
- (b) The minimum floor area of each dwelling unit shall be 28 square metres.
- (c) Vehicle car parking and access areas should not form a dominant element in the streetscape.

(16) *Intensive Livestock Operation's (ILO's)*

- (a) Intensive livestock operations involving 300 animal units or more will be permitted subject to the discretion of Council in accordance with the requirements contained herein. An expansion of an operation to provide for a greater number of animal units than the maximum number specified in the initial discretionary use approval, or any change in an operation which alters the species of animal reared, confined or fed in the operation, shall require a new discretionary approval. An application for an intensive livestock operation shall provide the following documentation to Council's satisfaction:
 - (i) that the water supply is sufficient for the development and the supply for neighbouring developments will not be adversely affected by the proposed operation;
 - (ii) of proposed methods of manure management, including on-site storage or stockpiling, transportation, and spreading, incorporation or disposal;

- (18) *Cannabis Retail Stores:*
- (i) municipal servicing capacity;
 - (ii) anticipated levels of noise, odour, smoke, fumes, dust, lighting, glare, vibration or other emissions emanating from the operation;
 - (iii) anticipated increased levels or types of vehicle traffic, unsafe conditions or situations for vehicles, cyclists or pedestrians; and
 - (iv) utilization of hazardous substances.
- (a) The location of cannabis retail stores will only favourably be considered where it can be demonstrated that the use and intensity is appropriate to the site and that it will have a minimal impact on the surrounding, adjacent areas, particularly residential areas.
- (17) *Cannabis Production Facilities:*
- (b) Council may require an applicant to utilize manure management practices or other technology that conventional stockpiling and spreading.
 - (vi) with applications for wild boar operations, of a containment plan being submitted, setting out in detail the techniques and methods to be used to keep wild boars. The containment plan shall also contain a contingency plan that sets out in detail how the operator will deal with escaped wild boar.
- (v) of the proposed methodology for monitoring on-site and neighbouring wells for water quality and quantity purposes after the LLO has begun operation, and for reporting on same to Council; and,
- (iv) of the location and extent of sufficient lands to use for the spreading of manure from an LLO, as well as proposals for the annual confirmation of the continues availability of lands;
- (iii) of proposed odour management and control measures, including storage facilities and liquid manure lagoons, and odour management control measures related to the ventilation of hog or poultry barns;

3.8 VALIDITY OF A DEVELOPMENT PERMIT

- 3.8.1 If development authorized by a development permit is not commenced within twelve (12) months of the date of issue, the permit ceases to be valid.
- 3.8.2 A development permit extension may be granted for an additional twelve (12) month period by the Development Officer.

3.9 AMENDING THE ZONING BYLAW

- 3.9.1 Any person seeking to amend this Zoning Bylaw may submit an application for such amendment and, upon payment of the required fee, the Development Officer shall refer such application to Council for consideration.
- 3.9.2 Council may authorize an amendment to a Zoning Bylaw, and that amendment shall be adopted by bylaw.
- 3.9.3 Sections 206 - 212 of *The Act*, shall govern the process to be followed with respect to public notice and public participation in the adoption of a bylaw proposed to amend this Zoning Bylaw.

3.10 DEVELOPMENT APPEALS BOARD

- 3.10.1 Council shall appoint a Development Appeals Board in accordance with Sections 49(j) and 213 to 227 of *The Act*.
- 3.10.2 A person who wishes to appeal to the Development Appeals Board shall, within 30 days of the date of issuance of or refusal to issue a development permit, file a written notice of intention to appeal, and the appeal fee, with the secretary of the Development Appeals Board.
- 3.10.3 A person whose application for a discretionary use or development has been approved with prescribed development standards may appeal any development standards considered excessive, to the Development Appeals Board.
- 3.10.4 An appellant shall make the appeal within 30 days of the date of the issuance of, or refusal to issue, a development permit.
- 3.10.5 Nothing in this section authorizes a person to appeal a decision of the council:
 - (1) refusing to rezone land; or,
 - (2) rejecting an application for approval of a discretionary use.

- 3.10.6 In making an appeal to the Development Appeals Board, and hearing such appeal, the provisions of *The Act* shall apply.

3.11 MINOR VARIANCES

- 3.11.1 Council may grant a variance of up to 10% of any yard requirement or minimum required distances between buildings for a use that conforms to this bylaw. All such variances shall be

(a)	General: Where a development or subdivision proposal involves a detailed RM review, a plan or Zoning Bylaw Amendment, a development agreement, serving a notice of proposed amendment and the costs associated with the publication of the proposed amendment in the newspaper of record.	Detailed review costs:
(2)	These fees shall be in addition to any fee required by Section 3.12.1 above.	
(i)	Development Appeal Fee: up to \$50.00 as specified by the Development Board	Development Appeal Fee:
(e)	Permitted oil & gas development: \$100.00	Discretionary accessory use:
(f)	Permitted ancillary use: \$100.00	Discretionary ancillary use:
(g)	Permitted non-farm accessory use: \$25.00	Discretionary oil & gas development:
(h)	Permitted principal use: \$25.00	Permitted oil & gas development:
(i)	Development Appeal Fee: up to \$50.00 as specified by the Development Board	Development Appeal Fee:
(a)	Permitted principal use: \$25.00	Permitted oil & gas development:
(b)	Permitted non-farm accessory use: \$25.00	Permitted ancillary use:
(c)	Permitted ancillary use: \$25.00	Permitted oil & gas development:
(d)	Permitted oil & gas development: \$100.00	Permitted oil & gas development:
(e)	Permitted accessory use: \$100.00	Permitted non-farm accessory use:
(f)	Permitted ancillary use: \$100.00	Permitted oil & gas development:
(g)	Permitted ancillary use: \$100.00	Permitted oil & gas development:
(h)	Permitted oil & gas development: \$200.00	Permitted oil & gas development:
(i)	Development Appeal Fee: up to \$50.00 as specified by the Development Board	Development Appeal Fee:
(a)	General: Where a development or subdivision proposal involves a detailed RM review, a plan or Zoning Bylaw Amendment, a development agreement, serving a notice of proposed amendment and the costs associated with the publication of the proposed amendment in the newspaper of record.	Detailed review costs:
(2)	These fees shall be in addition to any fee required by Section 3.12.1 above.	
(1)	An applicant for a development permit shall pay an application fee in accordance with the following:	

3.12.2 Application fees

In addition to an application fee, where a person requests Council to amend the Zoning Bylaw, that person shall pay to the municipality a fee equal to the costs associated with the public advertisement of the proposed amendment and the costs associated with the publication of the proposed amendment in the newspaper of record that is the subject of the proposed amendment.

3.12.1 Amendment of the Zoning Bylaw

3.12 FEES

3.11.2 Council shall maintain a registry of the location and all relevant details of the granting of such variances.

subject to the conditions and granted in accordance with the procedures contained in Section 60 of *The Act*.

- (3) Where a person applies to Council to amend the Zoning Bylaw, that person shall pay to the municipality the following application fees, where applicable:
- (a) Text amendments: \$200
 - (b) Map amendments (see table below):
 - Class 1 Districts: A,
 - Class 2 Districts: C1, M1,
 - Class 3 Districts: CR1, CR2, H

Zoning Map Amendments		To		
		Class 1	Class 2	Class 3
From	Class 1	\$200	\$400	\$800
	Class 2	\$200	\$400	\$800
	Class 3	\$200	\$200	\$600

Where an application to amend the Zoning Bylaw involves amendment within two or more of the above categories the sum of the amendment fees shall apply for all categories. These fees shall be in addition to any fee required by Section 3.12.1 above.

3.13 ZONING BY AGREEMENT

- 3.13.1 A zoning designation which is subject to an agreement entered into pursuant to the provisions of Section 69 of *The Act* and Section 5.1.4 of the Official Community Plan, shall be indicated on the Zoning District Map by the addition of the bylaw number authorizing the agreement after the zoning district designation.

3.14 OFFENCES AND PENALTIES

- 3.14.1 Pursuant to Section 242 of *The Act*, the Development Officer may inspect any development suspected of contravening *The Act*, or any regulation or bylaw made pursuant to *The Act*. If it is determined that a contravention exists, the Development Officer may notify the owner in writing and instruct the owner to correct the contravention within a set time period. If for any reason the contravention has not been corrected within that time, the Development Officer may extend the time period or issue a zoning compliance order pursuant to Section 242(4) of *The Act* to achieve bylaw conformance.
- 3.14.2 Any person who violates this Bylaw is guilty of an offence and is liable, on summary conviction, to the penalties provided by Section 243 of *The Act*.

4 GENERAL REGULATIONS

Except as noted, the following regulations shall apply to all zoning districts in this bylaw:

4.1 FRONTAGE ON THE ROAD

A development permit shall not be issued unless the site intended to be used, or upon which a building or structure is to be erected, abuts, or has frontage on a graded all-weather registered road, or unless satisfactory arrangements have been made with Council for the improvement or building of a road, where required.

A subdivision shall not be supported unless the proposed severance to be used, or upon which a building or structure is to be erected, abuts, or has frontage on a graded all-weather registered road, or unless satisfactory arrangements have been made with Council for the improvement or building of a road, where required.

4.2 DEVELOPMENT ON HAZARD LANDS

- 4.2.1 Where a proposed development of a building is to be located on land considered by Council to be potentially hazardous, including but not limited to a wetland, water body or watercourse where flooding may occur, the lands shall be deemed "hazardous" and Council shall require the applicant to submit sufficient topographic information to determine if the development will be within 50 metres of:
- (1) any slope(s) that may be unstable;
 - (2) any river or stream flood plain;
 - (3) any other land that may be subject to flooding; and/or,
 - (4) contaminated sites.
- 4.2.2 Council may require that before a permit may be issued, the applicant shall submit a report prepared by a professional competent to assess the suitability of the site for a development described in Section 4.2.1, and which in the opinion of Council, shows that the proposed site and development is suitable with respect to the following where relevant:
- (1) the potential for flooding up to the Safe Building Elevation, to be determined from specific site investigations, or where not involving any building, such lower elevation as may be suitable for the proposed use;
 - (2) the potential for slope instability; and/or
 - (3) the required mitigation measures for construction on areas of high water tables, in slopes or on contaminated sites if any.
- 4.2.3 Actions identified in an assessment prepared pursuant to Section 4.2.2 which prevent, change, mitigate or remedy hazards in lands deemed hazardous may be incorporated as conditions to issuance of any development permit that may be issued. Council shall refuse a permit for any

<p>4.3.1</p> <p>No building shall be moved within, or into, the municipality, without first obtaining a development permit, except as provided in Section 3.3, from the Development Officer.</p>	<p>development for which, in Council's opinion, the proposed actions are inadequate to address the adverse effects or will result in excessive municipal costs.</p>
<p>4.3</p> <p>BUILDING TO BE MOVED</p>	<p>Rural Municipality of Mountain View No. 318 Zoning Bylaw</p>
<p>4.4.1</p> <p>No development or use of land which requires sewage disposal or landfill facilities shall be permitted unless those facilities are approved by the Regional Health Authority and/or Saskatchewan Environment. Disposal of liquid, solid, or gaseous waste shall be governed by Acts administered by the Department of Agriculture and Food, Environment, Health and the Saskatchewan Watershed Authority.</p>	<p>Saskatchewan Environment. Disposal of liquid, solid, or gaseous waste shall be governed by Acts administered by the Department of Agriculture and Food, Environment, Health and the Saskatchewan Watershed Authority.</p>
<p>4.4</p> <p>WASTE DISPOSAL</p>	<p>Saskatchewan Environment. Disposal of liquid, solid, or gaseous waste shall be governed by Acts administered by the Department of Agriculture and Food, Environment, Health and the Saskatchewan Watershed Authority.</p>
<p>4.5.1</p> <p>No development or use of land shall be permitted where the proposal will adversely affect domestic and municipal water supplies, or where a suitable, potable water supply cannot be furnished to the requirements of the Regional Health Authority and/or the Saskatchewan Water Security Agency.</p>	<p>domestic and municipal water supplies, or where a suitable, potable water supply cannot be furnished to the requirements of the Regional Health Authority and/or the Saskatchewan Water Security Agency.</p>
<p>4.6</p> <p>STORAGE OF CHEMICALS, FERTILIZERS AND COMBUSTIBLE MATERIALS</p>	<p>The storage of chemicals, fertilizers and combustible materials are subject to the requirements of both the federal and provincial governments. All necessary approvals from other regulatory agencies must be obtained prior to issuance of a development permit. Development permits may include the requirement that all permits or licenses required by other regulatory agencies be obtained before development proceeds.</p>
<p>4.6.1</p> <p>The storage of chemicals, fertilizers and combustible materials are subject to the requirements of both the federal and provincial governments. All necessary approvals from other regulatory agencies must be obtained prior to issuance of a development permit. Development permits may include the requirement that all permits or licenses required by other regulatory agencies be obtained before development proceeds.</p>	<p>both the federal and provincial governments. All necessary approvals from other regulatory agencies must be obtained prior to issuance of a development permit. Development permits may include the requirement that all permits or licenses required by other regulatory agencies be obtained before development proceeds.</p>
<p>4.7</p> <p>ONE PRINCIPAL BUILDING PERMITTED ON A SITE</p>	<p>Not more than one principal building shall be permitted on any one site except for:</p> <ul style="list-style-type: none"> (1) public works; (2) institutional uses; (3) agricultural uses; (4) shopping centres; (5) dwelling groups; (6) manufactured homes in manufactured home courts; (7) recreation facilities; (8) schools; (9) hospitals; (10) municipal facilities; (11) communal dwellings; and, (11) ancillary uses.
<p>4.7.1</p> <p>Not more than one principal building shall be permitted on any one site except for:</p>	<ul style="list-style-type: none"> (1) public works; (2) institutional uses; (3) agricultural uses; (4) shopping centres; (5) dwelling groups; (6) manufactured homes in manufactured home courts; (7) recreation facilities; (8) schools; (9) hospitals; (10) municipal facilities; (11) communal dwellings; and, (11) ancillary uses.

4.8 NON-CONFORMING BUILDINGS, SITES AND USES

- 4.8.1 The adoption or amendment of this bylaw does not affect non-conforming buildings, sites and uses.
- 4.8.2 The provisions of *The Act*, Sections 88 to 93 inclusive, shall apply to all non-conforming buildings and uses.
- 4.8.3 Non-conforming buildings or sites may continue to be used, maintained and repaired in their present form.

4.9 MANUFACTURED HOMES

- 4.9.1 Wherever a single detached dwelling is allowed it may be in the form of a manufactured dwelling subject to Section 4.9.2.
- 4.9.2 Every manufactured home shall bear CSA A277 certification, or a replacement thereof, and shall be attached to a permanent foundation, or securely anchored to the ground and skirted, prior to occupancy.

4.10 PUBLIC WORKS, PIPELINES AND FACILITIES OF THE MUNICIPALITY

- 4.10.1 Public works and facilities of the Municipality, except solid and liquid waste disposal sites, shall be permitted uses in every zoning district, and unless otherwise specified by this bylaw, no minimum site or yard requirements shall apply.
- 4.10.2 Where a pipeline or other utility or transportation facility will cross a municipal road, Council may apply such special design standards as it considers necessary to protect the municipal interest in the existing and future improvements to the road.

4.11 VEHICLE STORAGE

- 4.11.1 Notwithstanding anything contained in this Bylaw, no person shall use any site in any country residential or hamlet district for the parking or storage of more than one (1) unlicensed vehicles outside of an enclosed building.
- 4.11.2 Sections 4.11.1 shall not apply to permitted machinery or automotive salvage yards, auction markets or agricultural implement, recreational vehicle, automobile, marine and manufactured home sales and service establishments.
- 4.11.3 Council may require that such vehicles be screened from roadways or neighbouring properties by landscape features or fences or a combination thereof.

- 4.12 MANURE DISPOSAL**
- (1) The use of agricultural land for the disposal and recycling of manure produced by an approved intensive livestock operation is permitted subject to the following regulations:
- (1) Manure spreading shall not occur within the required separation distances prescribed in Table 7-1.
- (2) Liquid manure shall be spread by direct injection into the soil.
- (3) Solid manure shall be incorporated into the soil within 24 hours.
- (4) Manure (solid nor liquid) shall not be spread on ground that is frozen or covered in frost or snow.
- 4.12.2 Upon application to Council, other procedures for disposal of manure may be approved where the applicant establishes to the satisfaction of Council that the objectives of the Official Community Plan will be achieved to a similar or better standard. Council may specify a limited time during which the approval will be valid.
- 4.12.3 Council may exempt in whole or in part an applicant from this section where each of the following are true:
- (1) the manure will be spread on land owned by the operator of the LLO and will not have a negative impact in neighboring properties, groundwater, or natural areas; and
- (2) adverse weather conditions prevent the incorporation of manure in which case incorporation of the spread manure may be delayed until weather conditions permit.
- 4.13 SPECIAL STANDARDS AND REGULATIONS
- 4.13.1 Accessory Uses, Buildings and Structures**
- (1) Accessory uses and buildings shall be subordinated to, and located on the same site at the principal building or use, and used in conjunction with that principal use.
- (2) Time of Construction:
- (a) Where a Development Permit has been issued for a principal building, Council may, at its discretion, allow prior development of an accessory building where such building is required for the storage of construction material or equipment. If the principal building is not completed in the time period required, the accessory building is to be removed.
- (3) Height of Accessory Buildings:
- (a) Residential and Hamlet Districts:

- (i) Detached accessory buildings in any hamlet district are not to exceed the height of the principal dwelling, and in no case shall an accessory building exceed a height of 5 metres.
 - (ii) Detached accessory buildings in any country residential development district: No height restrictions.
- (b) Agricultural, Commercial and Industrial Districts:
- (i) Detached accessory buildings in any agriculture district, commercial district or industrial district: No height restrictions.

(4) *Area of Accessory Buildings:*

The floor area off all principal and accessory buildings on a site shall not exceed the maximum site coverage, where required.

- (a) Residential Districts:
- (i) Detached accessory buildings in any country residential development district: No area restrictions.
- (b) Agricultural, Commercial and Industrial Districts:
- (i) Detached accessory buildings in any agriculture district, commercial district or industrial district - no area restrictions.
- (c) Where this bylaw specifies the maximum building floor area for accessory buildings, that area shall mean the combined building floor area of all accessory buildings on site.

(5) *Location of Accessory Buildings:*

(a) Residential and Hamlet Districts:

Detached accessory buildings in country residential district are subject to the following regulations:

- (i) *Front Yard:* minimum – 6 metres
- (ii) *Rear Yard:* minimum – 1.5 metres
- (iii) *Side Yard:* minimum – 1.5 metres

(b) Agricultural, Commercial and Industrial Districts:

Detached accessory buildings in any agricultural or commercial district are subject to the following regulations:

- (i) *Front Yard:* minimum - same as principal use

		a. Water and Sewer:
	(iii) Services:	
		not be used as garden suites in any other zoning district.
	(ii) Manufactured homes, subject to all wheels and axles being removed,	may be used as garden suites in the A - Agriculture District; they shall
	(i) Garden suites shall be constructed at grade and without a basement.	Garden suites shall be constructed at grade and without a basement.
	(d) a garden suite, subject to the following provisions:	
		removed from the site within 60 days of completing the work.
	(c) a temporary construction camp, tool shed, scaffold or other such building or other	located on the site where such work is underway and provided that it shall be such temporary work camp which is incidental to construction and provided it is removed from the site within 60 days of completing the work.
	(iv)	the minimum floor area of each dwelling unit shall be 28 square metres.
	(iii)	an emergency exit must be provided in addition to the main entrance; and
	(ii)	the commercial dwelling shall have a main entrance separate from that of the commercial or industrial establishment;
	(i)	the dwelling unit must be physically attached to the primary building where commercial or industrial operations are underway;
	(b)	business dwelling as a residence for an operator, manager, an employee and/or partner engaged in a commercial or industrial operation in a commercial or industrial zoning district, subject to the following provisions:
	(a)	a farm dwelling as a residence for an operator, or for employees and/or partners engaged in farm operation, intensive livestock operation, or intensive agricultural operation. Additional dwelling units may be allowed subject to intensive agricultural operation. Additional dwelling units may be allowed subject to a legitimate agricultural operation and if it is intended to accommodate farm workers, to a maximum of 3 additional dwellings. The granting of a development permit by Council for an additional dwelling(s) shall not be construed, in any way, as consent or approval for future subdivision.
(6)	Accessory dwelling units shall only be permitted to accommodate:	
	(iii) Side Yard: minimum - same as principal use, except campgrounds and tourist camps where the minimum shall be 7.5 metres home courts where the minimum shall be 7.5 metres	Rear Yard: minimum - same as principal use, except campgrounds, and manufacturer base camps, and tourist camps where the minimum shall be 4.5 metres and manufacturer base camps where the minimum shall be 7.5 metres
	(ii)	metres

A garden suite shall be connected to the water and sewer service of the principal residential buildings.

b. *Other Services:*

All other services (cable, electrical, natural gas, telephone) may have separate connections or connect to those services of the principal residential building.

(e) Communal dwelling(s) as residences for colonies, engaged in a farm operation, intensive livestock operations, or intensive agricultural operations, subject to the following provisions:

- (i) All dwelling(s) must be located on a site conforming to all requirements of the Zoning Bylaw.
- (ii) Utilities, including sewage disposal systems, must meet provincial standards.

(7) *Rental Suites:*

A Rental Suite may be attached as a discretionary use to any Single Detached Dwelling in any zoning district, subject to approval of a Building Inspector hired or contracted by the Rural Municipality. Rental Suites are subject to the following requirements:

- (a) Cooking facilities, food preparation, sleeping and sanitary facilities within the structure and which are physically separate from those of the principal dwelling.
- (b) The suite also has an entrance separate from the entrance to the principal dwelling, either from a common indoor landing or directly from the side or rear of the structure.

4.13.2 Campgrounds and Tourist Camps

- (1) The applicant for a development permit for a campground or tourist camp shall provide the Development Officer with a plan of the site, identifying any buildings, uses of land and the location of all roadways and recreation vehicle or tent campsites sites with dimensions. The addition or rearrangement of sites, the construction or moving of buildings, the material change in use of portions of land, or the filling or clearing of land shall require a development permit, and the applicant shall submit for approval an amended plan incorporating the proposed development.
- (2) A campground or tourist camp shall have, within its boundaries, a buffer area abutting the boundary of not less than 4.5 metres in width, which shall contain no buildings.
- (3) A site for each recreation vehicle and campsite permitted in the campground or tourist camp shall be designated and clearly marked on the ground.
- (4) Each site shall have a minimum area of 150 square metres.

- (1) Manufactured home courts shall have a minimum depth of not less than 7.5 metres in width, which shall contain no buildings or structures. Manufactured home courts shall have, within their boundaries, a buffer area abutting the boundary which shall:
- (a) have a minimum depth of not less than 7.5 metres in width, which shall contain no buildings or structures.
- (b) not contain any roads, except those which connect a public roadway to the road system within the manufactured home court.
- (2) Each manufactured home site permitted in a manufactured home court shall be designated and clearly marked on the ground.
- (3) Each manufactured home site shall have a minimum area of 379.8 square metres.
- (4) No portion of any manufactured home site shall be located within an internal roadway or required buffer area.
- (5) Each manufactured home shall have direct and convenient access to a developed internal roadway, which shall not be located in any required buffer area.
- (6) Each manufactured home shall be located at least 4.5 metres from any other manufactured home and each manufactured home site shall have dimensions, location and orientation sufficient to allow for such location of manufactured homes.
- (7) The space provided for roadways within a manufactured home court shall be at least 7.5 metres in width. No portion of any site, other use or structure shall be located in any 7.5 metres in width. Within a campground or tourist camp shall be at least 7.5 metres in width. Each recreation vehicle shall be located at least 4.5 metres from any other recreation vehicle and each site shall have dimensions, location and orientation sufficient to allow for such location of recreation vehicles.
- (8) The space provided for roadways within a campsite or tourist camp shall be at least 7.5 metres in width. No portion of any site, other use or structure shall be located in any 7.5 metres in width. No portion of any campsite or tourist camp shall be at least 7.5 metres in width. Each recreation vehicle shall have direct and convenient access to a developed internal roadway, which shall not be located in any required buffer area.
- (9) A campground or tourist camp may include, as an ancillary use, a laundromat or a convenience store designed to meet the needs of occupants of the sites and a one unit dwelling for the accommodation of the operator.
- (10) No recreation vehicle shall be stored on any campsite when the campground is not open.
- (11) The Public Health Act, and regulations passed thereunder, shall be complied with in respect of all operations and development of campgrounds.
- (12) Manufactured home courts shall have, within their boundaries, a buffer area abutting the boundaries of all other manufactured home courts.

4.13.3 Manufactured Home Courts

metres in width. No portion of any manufactured home site, other use or structure shall be located in any roadway.

- (8) A manufactured home court may include, as an ancillary use, a laundromat or a confectionary designed to meet the needs of occupants of the manufactured home court and a one unit dwelling for the accommodation of the operator.
- (9) *The Public Health Act*, and Regulations passed thereunder, shall apply to all operations and development of manufactured home courts.

4.13.4 Public Works in the Form of Solid and Liquid Waste Management or Disposal Facilities

- (1) Development and maintenance of a public work in the form of a solid or liquid waste disposal facility will be subject to the following special standards:
 - (a) A buffer strip containing trees, shrubs or a berm shall be located surrounding a lagoon or sanitary landfill disposal area.
 - (b) Any solid or liquid waste disposal facility shall be fenced.
 - (c) Adequate precautions shall be taken to prevent pollution of ground water by disposal operations.
 - (d) Solid waste disposal facilities shall be located in proximity to a provincial highway and adjacent to an all-weather road.
 - (e) The development of any new disposal sites shall take into consideration direction of prevailing winds.
 - (f) Further regulation of solid waste disposal sites may be achieved by adoption and administration of a Waste Management Bylaw.

4.13.5 Bed and Breakfast Homes and Vacation Farms

- (1) Bed and breakfast homes and vacation farms shall be subject to the following requirements:
 - (a) Vacation farms shall be ancillary to an agricultural operation and may include bed and breakfast, cabins and overnight camping areas.
 - (b) Bed and breakfast operations shall be located in, and ancillary to, a single detached dwelling used as the operator's principal residence developed as a farm operation site or country residence
 - (c) Only one sign, not exceeding 1.5 square metres in sign face area, advertising the vacation farm or bed and breakfast home, and located on-site, is permitted.
 - (d) Vacation farms and bed and breakfast homes shall be licensed pursuant to *The Public Health Act*, where tourist accommodations require health approval.

- (2) Where a gas bar is allowed to operate in conjunction with another use on a site, the following standards and regulations apply:
- (a) All fuel pumps and above ground storage tanks shall be at least five metres from any building on the site, and 6 metres from any site line.
 - (b) The site shall have at least two separate entrances for vehicles, at least 15 metres apart.
 - (c) Access to, and parking for, fuel dispensing apparatus shall not obstruct access to the site, or other required off street parking spaces on the site.
- (1) Where operated as the principal use on a site, gas bars are subject to the regulations and standards for service stations.
- (2) Where a gas bar is allowed to operate in conjunction with another use on a site, the following standards and regulations apply:
- (a) All fuel pumps and above grade level, shall be at least 6 metres from a site line.
 - (b) Fuel pumps and other apparatus for dispensing or storage of fuel, located all or partly above grade level, shall be at least 6 metres from a site line.
 - (c) Fuel pumps and other apparatus for dispensing or storage of fuel, located all or partly stored within a building.
 - (d) Where service stations occupy a corner site, only one access point shall be on the blanking street.

4.13.8 Gas Bars

- (1) No building or structure used for the purpose of keeping boarders or lodgers.
- (2) In any residential district, no exterior alterations shall be undertaken to a dwelling or former dwelling which would be inconsistent with the residential character of the building or property.
- (3) Required parking spaces shall not be located in a required front yard.
- (4) Residential care facilities and residential care facilities may be approved as an accessory use or as a principal use.
- (5) In addition to the development standards of the zoning district, custodial care facilities and residential care facilities that are listed as discretionary uses shall be reviewed and approved in accordance with Section 3.7.

4.13.7 Service Stations

- (1) Custodial care facilities and residential care facilities may be approved as an accessory use or as a principal use.
- (2) In any residential district, no exterior alterations shall be undertaken to a dwelling or former dwelling which would be inconsistent with the residential character of the building or property.
- (3) Required parking spaces shall not be located in a required front yard.
- (4) No building or structure used for the purpose of a custodial care facility or a residential care facility shall be used for the purpose of keeping boarders or lodgers.
- (5) In addition to the development standards of the zoning district, custodial care facilities and residential care facilities that are listed as discretionary uses shall be reviewed and approved in accordance with Section 3.7.

4.13.6 Custodial Care Facilities and Residential Care Facilities

- (e) Council may specify a maximum number of bedrooms, cabins or camping sites, or combination thereof, as a special standard in the issuing of a discretionary approval for a bed and breakfast home or vacation farm application.

4.13.9 Above Ground Fuel Storage Tanks

- (1) Above-ground fuel storage tanks which meet the standards of the National Fire Code may be permitted in association with service stations, gas bars and other permitted industrial or commercial uses where the dispensing of fuel to vehicles is a standard aspect of the use.
- (2) The total storage capacity for above-ground fuel storage tanks on any single service station or gas bar shall not exceed the regulations and requirements set out by the National Fire Code.
- (3) Above-ground fuel storage tanks shall be:
 - (a) located at least 3 metres from any property line or building; however, for uses other than gas bars and service stations, the 3 metre separation distance may be reduced to 1 metre for tanks with a capacity of 5,000 litres or less.
- (4) Notwithstanding subsection (2) above, above ground fuel storage tanks associated with a gas bar or service station shall be:
 - (a) located at least 6 metres from any property line or building.
 - (b) at least 15 metres from the boundary of any site within a Residential district.
- (5) The dispensing equipment associated with above-ground fuel storage tanks shall be located at least 3 metres from any property line, at least 7.5 metres from any open flame or other ignition source, and at least 4.5 metres from any door or window.
- (6) Notwithstanding (4) above, above ground fuel storage tanks associated with a gas bar or service station shall be located at least 6 metres from any property line, at least 7.5 metres from any open flame or other ignition source, and at least 4.5 metres from any door or window.
- (7) Above-ground fuel storage tanks shall be protected from vehicles with suitable posts, guardrails or other similar means.

4.13.10 Home Based Businesses and Farm Based Businesses

- (1) Home based businesses and farm based businesses shall be subject to the following development standards:
 - (a) The use is clearly ancillary to the use of a farm as an agricultural operation or the dwelling unit as a private residence.
 - (b) The operator of the business is a resident of the dwelling unit and, in the case of a farm based business only, up to five (5) non-resident employees may be employed at the site. Any employee shall be directly under the hire and management of the operator of the business. Where the business is a building or service contractor, additional employees may be involved only at the client building site.

- (1) Outside storage shall not be permitted at auction markets except for the display of motor vehicles, farm machinery, and heavy farm equipment.

4.13.14 Auction Markets

- (2) Outdoor animal enclosures may not be located in front yards.
- (1) An outdoor area must be provided for animals to run free, without being chained, in an area enclosed by a fence which provides safety for the animals and neighbours to the satisfaction of Council.

4.13.13 Kennels (Boarding and Breeding)

- (2) Dugouts may not be dug within 38 metres of an established dugout.
- (1) Dugouts, sewage lagoons and manure storage pits shall maintain a minimum separation distance of 15 metres from the legal boundaries of the surface parcel on which they are situated.

4.13.12 Dugouts, Sewage Lagoons and Manure Storage Pits

- (5) A use that is established as an ancillary use to an agricultural operation shall cease to be permitted when the operator ceases to be a resident on the site.
- (4) Outfitter base camps and tourism base camps may be ancillary to an agricultural operation for which a permit has been issued and located on the same site.

- (3) Council may establish standards limiting the total number of guests and rooms, and the location of buildings and accessory activities as a condition of issuing a discretionary use permit for outfitting base camps and tourism base camps. Any increase in the number of guest rooms shall require a new discretionary approval.

- (2) All accommodation provided in conjunction with outfitter base camps and tourism base camps shall comply with *The Public Health Act*, and Regulations passed thereunder.
- (1) All outfitter base camps shall be located at least 305 metres from a dwelling unit that is not part of the operation.

4.13.11 Outfitter Base Camps and Tourism Base Camps

- (e) All permits issued for home based businesses shall be subject to the condition that the permit may be revoked at any time if, in the opinion of Council, the conditions under which the permit was originally issued are no longer met.
- (d) The permitted use shall be valid only during the period of time the property is occupied as a residence of the applicant for such permitted use.
- (c) No variation in the residential or residential farm character and appearance of the dwelling, ancillary residential building, or land shall be permitted.

- (2) Council may require that additional parking spaces be provided for auction markets.
- (3) Temporary storage and accessory repair of goods and materials to be sold shall be permitted.
- (4) Wrecking, destruction or dismantling of goods and materials shall not be permitted.

4.13.15 Truck Stops

- (1) Truck stops shall not be constructed within 300 metres of a school, education facility, playground, library or place of worship.
- (2) The minimum width of a driveway in a truck stop shall be 9.2 metres.
- (3) No more than two access driveways shall connect a truck stop to any street.
- (4) Gas bars on the site of a truck stop shall comply with Sections 4.13.8 and 4.13.9.
- (5) Above ground fuel storage tanks shall comply with Section 4.13.9.

4.13.16 Satellite Dishes and Solar Collectors

- (1) The installation and operation of a free standing satellite dish or solar collector, and their supporting structures shall be permitted in all zoning districts, subject to the following:
 - (a) in any District such structures shall not be located in any front yard, side yard and in the case of a corner site, in any portion of the rear yard which is within three (3) metres of the side property line adjacent to a flanking street unless it is screened from the flanking street to the satisfaction of the Development Officer;
 - (b) in any District such structures, if freestanding, shall not exceed a height of ten (10) metres above grade level;
 - (c) in any District such structures if attached to a principal building, shall not exceed a height of ten (10) metres above the lowest elevation of: roof surface of a flat roof; the decking of a mansard roof; and the eaves of a gable, hip or gambrel roof; and,
 - (d) in any District such structures, if attached to or erected upon an accessory building, shall not exceed the maximum permitted height of the accessory building upon which such structure is attached or erected.

4.13.17 Wind Energy Facilities (one turbine)

- (1) Wind energy facilities shall be accommodated as a discretionary use in each zoning district in this Bylaw, either as an accessory use to an established principal use on a site or as the principal use of a site. The following standards apply to wind energy facilities:
 - (a) Wind turbines are limited to a maximum height of 50 metres.

- (1) Wind Farms shall be accommodated as a discretionary use in the A - Agriculture District, either as an accessory use to an established principle use on a site or as the principle use of a site. The following standards apply to Wind Farms:
- (a) Wind turbines are limited to a maximum height of 50 metres.
 - (b) Wind turbines are limited to a maximum name plate capacity of 100kW.
 - (c) The setback of a wind turbine to any public road right of way and railway right of way that existed on the day the proponent submitted an application to the Municipality to construct, install or expand the wind energy facility, shall be greater than or equal to the height of the wind turbine.
 - (d) The setback of a wind turbine to any property boundary of a Non-Participating Noise Recipient that existed on the day the proponent submitted an application to the Municipality to construct, install or expand the wind energy facility, shall be greater than or equal to the height of the wind turbine.
- (2) Council will evaluate Discretionary Use applications for single wind turbines with the nearest non-participating noise receptor in the following way:
- (a) Wind turbines with a rotor diameter between 0.1 m and 5.0 m: 100 metre separation distance;
 - (b) Wind turbines with a rotor diameter between 5.01 and 12.5 m: 250 metre separation distance;
 - (c) Wind turbines with a rotor diameter greater than 12.5 m: 350 metre separation distance.
- (3) Council may approve a lesser separation where the applicant submits a copy of the agreement between the developer of a wind turbine and the Non-Participating Noise Recipient, agreeing to a lesser separation. Such agreements must contain the provision that parties to the agreement will register an interest in the titles of the affected land. Where such agreements are made, Council shall be a party to the agreement and may use Section 23 of The Act to register and be a party to the affected land.
- (4) The setback of a wind turbine to any property boundary of a Non-Participating Noise Recipient that existed on the day the proponent submitted an application to the Municipality to construct, install or expand the wind energy facility, shall be greater than or equal to the height of the wind turbine.
- (5) The setback of a wind turbine to any public road right of way and railway right of way that existed on the day the proponent submitted an application to the Municipality to construct, install or expand the wind energy facility, shall be greater than or equal to the height of the wind turbine.
- (6) The setback of a wind turbine to any property boundary of a Non-Participating Noise Recipient that existed on the day the proponent submitted an application to the Municipality to construct, install or expand the wind energy facility, shall be greater than or equal to the height of the wind turbine.
- (7) Wind turbines are limited to a maximum name plate capacity of 100kW.

greater than or equal to the height of the wind turbine.

- (e) Council may approve a lesser separation where the applicant submits a copy of the agreement between the developer of a wind turbine and the Non-Participating Noise Receptor, agreeing to a lesser separation. Such agreements must contain the provision that parties to the agreement will register an interest on the titles of the affected land. Where such agreements are made, Council shall be a party to the agreement and may use Section 235 of *The Act* to register an interest to the title(s) of the affected lands.
- (2) Council will evaluate Discretionary Use applications for Wind Farms with the following criteria:
 - (a) In addition to the criteria outlined in Section 4.13.17 (2), Wind Farms shall be separated from the nearest non-participating noise receptor by a distance of 550 metres.

4.13.19 Dwelling Groups and Communal Dwellings

- (1) Dwelling groups are subject to the following additional standards:
 - (a) The minimum side yard shall be measured from the closest main wall of the principal building closest to the side site line.
 - (b) All principal buildings forming part of the group shall be located from any other principal building in the group at a distance that meets The National Building Code of Canada and The National Fire Code of Canada.
 - (c) Council may apply special development standards regarding "yard requirements" to reduce conflict with neighbouring uses.

4.13.20 Temporary Work Camps

- (1) Temporary work camps shall be temporary and permitted only for a period not exceeding one (1) year as negotiated by Council.
- (2) The site shall be left in the condition agreed upon in the Development Permit, after the occupancy period.

4.13.21 Transloading Facilities for Oil and Gas Resources

Transloading facilities for Oil and Gas Resources shall be subject to the following requirements:

- (1) In addition to any other information required by Council, the applicant shall submit, as part of their development permit application, information regarding any hazardous material to be kept or stored on site, an emergency management plan, a screening and landscape plan, as well as site grading and drainage plans.
- (2) Transloading facilities for oil and gas resources shall not be located within 90 metres of a residence or on hazard lands.

4.13.23 Oil and Gas Development

(1) Exploration and development of oil and gas shall be subject to all federal and provincial separation distances for livestock facilities.

(b) Building development, as defined this bylaw, located on the same site and accessory or ancillary to the livestock facility, shall not be subject to minimum separation distances for livestock facilities.

(i) Council may approve a lesser separation than set out in (a) above where the applicant submits a copy of an agreement between the operator of the livestock facility and the owner(s) of the other affected development that specifies between operators and an owner (owners) of another development (as appropriate), agreeing to such lesser separation. Such urban Council (as appropriate), agreeing to such lesser separation, the applicant submits a copy of an agreement between the operator of the development (other development) and the owner(s) of the other affected development or the developer of the affected land.

(a) distances to the nearest land uses, development types and municipal limits, whether within the municipality or within an adjacent municipality, listed in Section 7, Table 7-1 Required Separation Distances Between Uses of this Zoning Bylaw and measured as specified in the notes to that table. These minimum separation distances shall apply to both development, alteration or expansion of livestock facilities and to other development proposed in the vicinity of existing intensive Livestock Operation, where the applicant establishes that the development will minimize the potential for conflict with adjoining uses in accordance with the following provisions:

(2) An application for an intensive livestock operation shall provide the following documentation:

(1) Intensive livestock operations involving 300 or more animal units or more will be permitted subject to the discretion of Council in accordance with specific requirements contained herein. An expansion of an operation to provide for a greater number of animal units than the maximum number specified in the initial discretionary use approval, change in an operation which alters the number of animal species or any change in an operation which alters the potential for animal rearing, confinement or handling, shall require a new discretionary use approval.

4.13.22 Intensive Livestock Operations (ILO's)

(5) Transloading facilities shall be developed and shall operate in compliance with all relevant federal and provincial regulations.

(4) Council may require the developer to undertake specific safeguards to address safety issues related to material kept on the site and nuisance issues related to dust, noise, odour, smoke, or similar conditions.

(3) The applicant shall suitably screen and landscape the facility from neighbouring properties to the satisfaction of Council.

requirements, and such activity must comply with the objectives and policies outlined in the Rosetown Hub and Spoke District Plan.

- (2) Oil and gas exploration, extraction and development within the RM shall occur in accordance with *The Oil and Gas Conservation Regulations, 2012*.
- (3) Multiple parcel country residential subdivisions, single parcel country residences and residential sites located in proximity to oil wells may be subject to separation requirements from an oil well, as per *The Subdivision Regulations*.
- (4) Multiple parcel country residential developments, single parcel country residences and residential sites located in proximity to sour gas wells with H₂S concentrations over 100 ppm may be subject to separation requirements based on guidelines as recommended by the Ministry of Government Relations.
- (5) In addition to any other information required by Council, the applicant shall submit, as part of their development permit application, information regarding any hazardous material to be kept or stored on site, an emergency management plan, a screening and landscape plan, as well as site grading and drainage plans.
- (6) The applicant shall suitably screen and landscape the facility from neighbouring properties to the satisfaction of Council.
- (7) Council may require the developer to undertake specific safeguards to address safety issues related to material kept on the site and nuisance issues related to dust, noise, odour, smoke, or similar conditions.

4.13.24 Abattoirs, meat processing and kill facilities

- (1) Shall be located at least 91.4 metres from residential areas, schools, hospitals, motels and restaurants.

4.13.25 Bulk Petroleum Tanks

- (1) Shall be located at least 91.4 metres from residential areas, schools, hospitals, and motels.

4.13.26 Solar Farms

- (1) In addition to any other information required by Council, the applicant shall submit, as part of their development permit application, information regarding site grading along with a drainage plan for the site.
- (2) Council may require that it be demonstrated how any adverse effects on neighbouring properties will be mitigated including ensuring that sight lines are maintained.

4.13.27 Cannabis Production Facilities

- (1) No outside storage is permitted.

- (2) window sills, eaves, gutters, belt courses, pilasters or other similar vertical columns;
- (1) steps 1.6 metres or less above grade level, as measured at the highest point of the steps, that are necessary for access to a permitted building or for access to a site from a street or lane;
- 4.16.2 The following yard encroachments shall be permitted in any required yard:
- (2) any private garage attached to a principal building.
- (1) any deck or floor area attached to a principal or accessory building that has a permanent roof structure and/or solid glass, or screen walls; and,
- 4.16.1 The following are not considered encroachments and shall be considered part of the principal or accessory building and all applicable regulations will apply to it as it would be to the principal or accessory building and all adjacent sites and public thoroughfares.
- (3) Unless otherwise directed by this Bylaw, garbage and waste material shall be stored in weatherproof and animal-proof containers and shall be visually screened from all adjacent sites and public thoroughfares.
- (2) Outside storage in a side or rear yard shall be screened from adjacent sites by a fence at least 1.9 metres in height, or a combination of fence and soft landscaping screening a minimum of 1.9 metres in height.
- (1) No outside storage shall be located in the front yard, except for the neatly arranged display of items for sale.
- 4.15.1 Where permitted in association with any approved industrial or commercial land use, all outside storage, including storage of garbage or waste materials, is subject to the following requirements:

- ### 4.15 OUTSIDE STORAGE AND WASTE MATERIAL STORAGE
- 4.14.1 The minimum setback of buildings, including dwellings, signs, trees, fences and other permanent structures from the centre line of a municipal road allowance, grid road, main farm access road or provincial highway on all sites shall be 45 metres (150 feet). On provincial highways and interstructures the minimum setback shall be regulated by the Ministry of Highways and Infrastructure. Development of buildings, signs, trees, fences and other permanent structures on sites that do not affect such roads shall observe the minimum front yard setbacks as identified in the specific regulation for those districts. Council may, by resolution, prescribe a lesser setback providing that the proposed development does not create a road intersection visibility or road maintenance issue.
- 4.15.1 Where permitted in association with any approved industrial or commercial land use, all outside storage, including storage of garbage or waste materials, is subject to the following requirements:

- ### 4.14 SETBACK FROM LINE OF ROADS
- (1) Cannabis retail stores shall maintain a minimum setback of 150 metres from schools, public playgrounds, public parks and licensed daycares.
- 4.13.28 Cannabis Retail Stores

cornices, bay windows, chimneys and similar non-structural alterations may project a distance of 0.6 metres from the building into any required yard, but not closer than 0.5 metres to a site line;

- (3) raised patios, decks and sidewalks not more than 0.6 metres above grade level, as measured at the outside edge of the patio, deck or sidewalk.
- (4) trees, shrubs, walkways, trellises or flag poles, so long as these fixtures do not extend into or over public land; and,
- (5) lighting fixtures and lamp posts.
- (6) In rear yards:
 - (i) raised patios and decks measuring more than 0.6 metres in height above grade, and canopies and balconies having a projection of not more than 3.0 metres into the required rear yard, provided they are located at least 3.0 metres from the rear site line.
- (7) In side yards:
 - (i) raised patios and decks measuring more than 0.6 metres in height above grade, and canopies and balconies provided they do not project into more than 25% of the required side yard.

4.17 PROHIBITED USES IN ALL DISTRICTS

- 4.17.1 The breeding of rats and other rodents and crickets and other insects is prohibited in all zoning districts in the municipality.

4.18 BUILDING LINES

- 4.18.1 Where a building line in a residential district has been established by existing buildings in a block having at least one half of the lots built on, new development may conform to this line.

4.19 BARE LAND CONDOMINIUMS

- 4.19.1 Regulations and development standards for buildings, uses and sites in all zoning districts shall also apply to uses and bare land units that are part of a bare land condominium plan.

4.20 DEPTH TO FRONTAGE RATIO

- 4.20.1 Depth to frontage ratio for residential sites: No restrictions.

4.21 TEMPORARY USES

- 4.21.1 Temporary uses will be permitted where appropriate in individual zoning districts at the discretion of Council.

- (1) Shipping containers shall be permitted in all districts, but are limited to one (1) in the CR1, CR2 and H Districts.
- (2) Shipping containers, permitted under subsection (1), shall only be used for shipping storage purposes accessory to the principal use of the site and shall comply with the requirements for accessory buildings for the applicable zoning district. In no case shall shipping containers be used for human habitation.
- (3) Shipping containers, permitted under subsection (1), shall:
- (a) be properly anchored and maintained in good repair;
 - (b) be sanded or sandblasted and repainted to a neutral colour prior to their placement, above grade, on a site;
 - (c) be located a minimum of 3.0 metres from, and behind the rear wall of, the principal building;
 - (d) meet the requirements of *The National Building Code of Canada* as applicable;
 - (e) in any district:
- Notwithstanding subsection (1), shipping containers may be temporarily placed on a site during active construction on a site when the shipping container is solely for the storage of supplies and equipment that are used for the site, provided that a valid building permit has been issued for construction on the site. The shipping container must be removed from the site upon completion of the construction, or use for a period of not more than 10 days in any six month period; and in any case, for a period of not more than 30 days unless an extension has been granted by the development officer to a maximum of 90 days.
- (4) Notwithstanding subsection (1), shipping containers may be temporarily placed on a site in any district:
- (a) when the shipping container is soleiy for the purpose of loading and unloading of items associated with the principal building for a period of not more than 10 days in any six month period; and
 - (b) for the purpose of loading and unloading of items associated with the principal building for a period of not more than 30 days unless an extension has been granted by the development officer to a maximum of 90 days.
- (5) When placed on a site pursuant to subsection (4), the shipping containers shall:

- ## 4.22 SHIPPING CONTAINERS
- 4.21.2 All temporary uses must be located on an existing site, no subdivision will be permitted for temporary uses.
- 4.21.3 Any buildings placed on sites where a temporary use is permitted must be removed on or before the expiry period allowed for the use, unless the construction of a permanent building is specifically permitted by Council.
- 4.21.4 The site must be restored to the same condition as it was prior to the beginning of the temporary use once the temporary use has ceased.
- 4.21.5 Council may require a performance bond from the applicant to ensure acceptable remediation of the site.

- (a) be located so as not to create a safety hazard; and
- (b) not be located within 1.2 metres of the interior edge of a sidewalk.

4.23 REGULATIONS FOR SIGNS AND BILLBOARDS

4.23.1 Signs Located in Highway Sign Corridor

- (1) Signs located in a highway sign corridor shall be regulated by the requirements of "*The Erection of Signs Adjacent to Provincial Highway Regulations, 1986*" and amendments thereto, and Section 4.23.2 shall not apply.

4.23.2 Third-Party Advertising Signs

- (1) Third-party advertising signs shall be prohibited in all zoning districts, except signs in the highway sign corridor which comply with Section 4.23.1. In all cases, signs affixed to or painted on a vehicle or trailer, shall be prohibited in all zoning districts.

4.23.3 General Sign Regulations

- (1) Signs for Cannabis Production Facilities and Cannabis Retail Stores shall not contain any cannabis-related images and are subject to the additional regulations in Section 4.23.

5 ZONING DISTRICTS

5.1 CLASSIFICATION OF ZONING DISTRICTS

- 5.1.1 In order to carry out the purpose and provisions of this Bylaw, the Rural Municipality is divided into the following Zoning Districts, the boundaries of which are shown on the "**Zoning District Map**". Such districts may be referred to by the appropriate symbols.

Districts	Symbols
Agriculture	A
Low Density Country Residential	CR1
Medium Density Country Residential	CR2
Hamlet District	H
Commercial and Light Industrial	C1
Industrial	M1

5.2 ZONING DISTRICT MAPS

- 5.2.1 The map, bearing the statement "This is the Zoning District Map which accompanies Bylaw Number _____ adopted by the Rural Municipality of Mountain View No. 318" and signed by the Reeve and Rural Municipal Administrator under the seal of the Rural Municipality shall be known as the "**Zoning District Map**" and such map is hereby declared to be an integral part of this Bylaw.

5.3 BOUNDARIES

- 5.3.1 The boundaries of such districts referred to, together with explanatory legend, notation and reference, are shown on the map entitled "**Zoning District Map**".
- 5.3.2 All streets, lanes and road allowances, if not otherwise specifically designated, shall be deemed to be in the same zoning district as the property immediately abutting upon such streets, lanes and road allowances. If the land abutting each side of a street, lane or road allowance is located in different zoning districts, the centre line of such street, lane or road allowance shall be deemed to be the district boundary, unless otherwise specifically designated.
- 5.3.3 Streets, lanes, and road allowances which are shown on the "**Zoning District Map**" and which have been permanently closed pursuant to Section 13 of *The Municipalities Act*, shall be in the same district as the land abutting both sides of the permanently closed street, lane or road allowance. If the land abutting each side of the permanently closed street, land or road allowance was located in different zoning districts before the said street, lane or road allowance was permanently closed, the centre line of such permanently closed street, lane or road allowance shall be deemed to be the district boundary, unless otherwise specifically designated.
- 5.3.4 In unsubdivided land, the zoning district boundary shall be determined by the scale shown on the "**Zoning District Map**".

- 5.4 REGULATIONS**
- 5.4.1 Regulations for the zoning districts are outlined in the following sections of this Bylaw.
- 5.5 PROPERTIES WITH MORE THAN ONE ZONING DISTRICT**
- 5.5.1 Where a site or lot is divided into more than one zoning district, each portion of the site or lot shall be developed and used in accordance with the provisions of the applicable zoning district.
- 5.6 TRANSITIONAL ZONING PROVISIONS**
- 5.6.1 Existing Buildings
- BUILDINGS lawfully existing at the time of the approval of this bylaw shall be limited in terms of site width and setback requirements, to the regulation of the zoning district in which they are located, or to their current dimensions, whichever is the least restrictive.

6 DISTRICT SCHEDULES

6.1 A – AGRICULTURE DISTRICT

6.1.1 Intent

The objective of the A - Agriculture District is to provide for the primary use of land in the form of agricultural development, associated residences, limited single-parcel country residential development, location-dependent natural resource development and other uses compatible with agricultural development.

6.1.2 Permitted and Discretionary Uses and Development Standards

The permitted and discretionary uses and applicable development standards are laid out in Table 6-1.

6.1.3 Prohibited Uses

Uses prohibited in the A - Agriculture District are as follows:

6.1.4 Accessory Buildings

- (1) Accessory buildings and uses, including accessory dwelling units, shall be permitted subject to Section 4.13.1.

6.1.5 Regulations

(1) Site Requirements

- (a) Minimum and maximum site size, site width, and yard requirements are shown in Table 6-1.

(2) Separation distances

- (a) Required separation distances are shown in Table 7-1.

6.1.6 Standards for Discretionary Uses

Council will consider discretionary use applications in the A - Agriculture District with regard to Section 3.7.2 Discretionary use Evaluation Criteria and Section 3.7.3 Terms and Conditions for Discretionary Use Approvals as well as additional development standards noted as follows.

(1) Discretionary Commercial Uses

- (a) Where ancillary to a farm operation, or single detached dwelling, Council may prescribe specific development standards in the issuing of a development permit limiting the size of operation, buildings used for the operation, and number of non-resident employees. Any increase in the area of land for a commercial use, or the number or size of buildings used for the commercial operation, shall

To retain the agricultural character of the municipality, a maximum of four (4) subdivisions per quarter-section will be allowed to be subdivided for non-farm county residential (where the essential land requirement is for a residential building site and space rather than for productive agricultural purposes) on a discretionary basis in the A - Agriculture District.

6.1.10 Single Parcel Residential

- (8) It will accommodate a new railway or road right-of-way.
 - (7) It is intended to avoid unnecessary changes to, or to work with, the natural vegetation pattern or topography of the area.
 - (6) It will accommodate the purchase or lease of Crown land.
 - (5) It is intended to accommodate estate planning or settlement.
 - (4) The agricultural parcel created results from the subdivision of land for purposes consistent with the objectives and policies in the Rosetown Hub and Spoke District Official Community Plan.
 - (3) It is intended to be consolidated under one title with adjacent land, in accordance with *The Land Titles Act, 2000*, to create a more viable agricultural unit.
 - (2) It is fragmented from the balance of the quarter section by either natural (river, creek, coulee, etc.) or manmade (roadway, railway, etc.) barriers.
 - (1) The severity of a financial crisis for a particular agricultural operation is demonstrated, in Council's opinion, to warrant the subdivision of a smaller site to assist debt restructuring or settlement.
- any of the following scenarios:
- Land into smaller than a quarter section for legitimate agriculture purposes will be permitted under In general, the fragmentation of agricultural holdings is not encouraged. However, subdivision of Council's opinion, to warrant the subdivision of a smaller site to assist debt restructuring or settlement.

6.1.9 Agricultural Subdivision

Outside storage, including garbage storage, is subject to Section 4.16 of this Bylaw.

6.1.8 Outside Storage

Exceptions to development standards in A - Agriculture District, are as follows:

6.1.7 Exceptions to Development Standards

- (b) Council may specify specific development standards for the location, setback, or screening of any area devoted to the outdoor storage of machinery, vehicles, or vehicle parts in conjunction with a commercial operation including any salvage or vehicle storage yard.
- require a new discretionary approval by Council.

- (1) Council may permit a larger or smaller site size than what is outlined in Table 6-1 to:
 - (a) minimize prime agricultural land being taken out of production;
 - (b) accommodate existing developed farm yard sites;
 - (c) accommodate sites fragmented from the balance of a quarter section by either natural (river, creek, coulee, etc.) or man-made (developed road, railway, etc.) barrier; or
 - (d) accommodate larger sites that include poor agricultural land.
- (2) Additional residential subdivision(s) in the A – Agriculture District may be permitted to be subdivided from a quarter-section for:
 - (a) any site fragmented from the balance of a quarter section by either natural (river, creek, coulee, etc.) or man-made (developed road, railway, etc.) barriers; or
 - (b) A previously developed, but now unoccupied farm site.
- (3) In order to minimize conflict between multiple lot residential subdivisions and other development, Council shall observe the separation distances set out in Table 7-1.
- (4) Council may approve a lesser separation than set out in Table 7-1 where the proposed development will not conflict with the long term future development of an adjoining urban municipality as demonstrated by the urban Council or where the applicant and the owner(s) of another affected development, agreeing to such lesser separation. Such agreements between an owner or owner(s) of the other development(s) must contain the provision that the parties to the agreement will register an interest to the titles of the affected land. Where such agreements are made, Council shall be party to the agreement and may use Section 235 of *The Act* to register an interest to the title(s) of the affected lands.

6.1.11 Temporary Accommodation

A manufactured home or a recreational vehicle may be permitted for a period of up to one year on an existing farm dwelling or residential site, while a permanent dwelling unit is being erected on the same site, subject to a resolution of council and the following conditions:

- (1) Adherence to a Trailer Bylaw (where applicable), securing a license on an annual basis.
- (2) Connection to sewer and water systems in accordance with the Department of Health.
- (3) Issuance of a development permit to the land owner on behalf of the occupant, issued on an annual basis.
- (4) Any other conditions which council may specify that ensure the adherence to this Bylaw.

A communal dwelling may be permitted, subject to discretionary use approval, by resolution of Council, if accessory to a legitimate agricultural operation and if it is intended to accommodate farm workers. The granting of a dwelling development permit by Council for an additional farm dwelling shall not be construed, in any way, as consent or approval for future subdivision.

One farm dwelling will be permitted as an accessory use to a farm operation. Two additional dwelling units may be allowed subject to discretionary use approval, by resolution of Council, if accessory to a legitimate agricultural operation and if it is intended to accommodate farm workers. The granting of a dwelling development permit by Council for an additional farm dwelling shall not be construed, in any way, as consent or approval for future subdivision.

6.1.13 Communal Dwellings

A communal dwelling may be permitted, subject to discretionary use approval, by resolution of Council, if accessory to a legitimate agricultural operation. The granting of a communal dwelling development permit by Council shall not be construed, in any way, as consent or approval for future subdivision. Communal dwellings are subject to Sections 4.13.1(e) and 4.13.19.

6.1.12 Accessory Dwelling Units

TABLE 6-1:
A - AGRICULTURE DISTRICT DEVELOPMENT STANDARDS

		Development Standards					
		Use		Minimum Front Yard (m)		Minimum Rear Yard (m)	
		Permitted or Discretionary	Subject to Sections	Minimum Site Area (ha)	Minimum Site Width (m)	Minimum Side Yard (m)	Minimum Rear Yard (m)
Agricultural Uses							
(1)	Agricultural support services	D		0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet
(2)	Farm operations	P	6.1.9 160 acres	64 ⁽²⁾ 160 acres	--	30 98.4 feet	35 114.8 feet
(3)	Intensive livestock operations	D	3.5.2 (2) 3.7.4 (16) 4.13.22 Table 7-1	1.0 2.47 acres	--	30 98.4 feet	35 114.8 feet
(4)	Intensive agricultural operations	D	3.5.2 (3) 0.8 2.0 acres	0.8 2.0 acres	--	30 98.4 feet	35 114.8 feet
Resource Based Uses							
(1)	Mineral exploration and extraction, excluding gravel pits	P	4.13.23	--	--	--	--
(2)	Petroleum exploration or extraction wells and related facilities	P	4.13.23	--	--	--	--
(3)	Petroleum pipelines, oil & gas wells, and related facilities	P	4.13.23	--	--	--	--
(4)	Petroleum related commercial uses	D	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 ⁽¹⁾ 32.8 feet
(5)	Solar farms	D	4.13.26 0.8 2.0 acres	0.8 2.0 acres	--	30 98.4 feet	35 114.8 feet
(6)	Transloading facilities for oil and gas resources	P	4.13.21	--	--	--	--
Residential Uses							
(1)	Dwelling units as an accessory use, except the first farm dwelling (3)(4)	D	4.3.10 Table 7-1	(5)	--	30 98.4 feet	35 114.8 feet
						10 32.8 feet	10 32.8 feet

**TABLE 6-1:
A - AGRICULTURE DISTRICT DEVELOPMENT STANDARDS**

Use	Development Standards						
	Minimum Site Width (m)	Minimum Yard Side Width (m)	Minimum Front Yard Side Width (m)	Minimum Rear Yard Side Width (m)	Maximum Site Area (ha)	Minimum Site Area (ha)	Subject to Selections or Discretionary Permitted or Subject to Selections or Discretionary
(2) Farm Dwellings	P	4.13.10 Table 7-1	(5)	30 98.4 feet	35	10 32.8 feet	10 32.8 feet
(3) Single detached dwellings (as a principal use)	D	Table 7-1 6.1.10	4.05 ⁽⁶⁾ 10.0 acres	16.2 ⁽⁶⁾ 40.0 acres	30 98.4 feet	35 114.8 feet	10 32.8 feet
Commercial Uses							
(1) Agriculture servicing and contracting establishments	D	3.7.4 (11)	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 32.8 feet
(2) Bed and breakfast homes	D	4.13.5	4.05 ⁽⁶⁾⁽⁷⁾ 10.0 acres	16.2 ⁽⁶⁾⁽⁸⁾ 40.0 acres	30 98.4 feet	35 114.8 feet	10 32.8 feet
(3) Campgrounds	D	3.5.2 ⁽¹⁾ 3.7.4 ⁽⁹⁾ 4.13.2	0.8 2.0 acres	--	30 98.4 feet	35 114.8 feet	10 32.8 feet
(4) Cannabis production facilities	D	3.7.4 (17) 4.13.27 4.23	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 32.8 feet
(5) Custodial care facilities	D	4.13.6	4.05 ⁽⁶⁾⁽⁷⁾ 10.0 acres	16.2 ⁽⁶⁾⁽⁸⁾ 40.0 acres	30 98.4 feet	35 114.8 feet	10 32.8 feet
(6) Drive-in theatres	D	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 32.8 feet	10 32.8 feet
(7) Golf courses	D	3.7.4 (10)	1.0 2.47 acres	--	-- 114.8 feet	35 114.8 feet	10 32.8 feet
(8) Grain elevators	D	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 32.8 feet	10 ⁽¹⁾ 32.8 feet
(9) Health care clinic	D	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 32.8 feet	10 32.8 feet
(10) Gravel pits and gravel crushing operations	D	3.5.2 (10) 3.7.4 (3) Table 7-1	--	--	--	--	3 9.8 feet

TABLE 6-1:
A - AGRICULTURE DISTRICT DEVELOPMENT STANDARDS

Use	Permitted or Discretionary	Subject to Sections	Development Standards				
			Minimum Site Area (ha)	Maximum Site Area (ha)	Minimum Site Width (m)	Minimum Front Yard (m)	Minimum Side Yard (m)
							Minimum Rear Yard (m)
(11) Home based businesses and farm based businesses	D	4.13.10	4.05 (6)(7) 10.0 acres	16.2 (6)(8) 40.0 acres	30 98.4 feet	35 114.8 feet	10 32.8 feet
(12) Kennels	D	4.13.13	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 32.8 feet
(13) Machine shops and metal fabricators	D	3.7.4 (6)	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 (1) 32.8 feet
(14) Meat processing and kill facilities	D	4.13.24	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 (1) 32.8 feet
(15) Outfitter base camps	D	3.5.2 (1) 4.13.11	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 32.8 feet
(16) Residential care facilities	D	4.13.6	4.05 (6)(7) 10.0 acres	16.2 (6)(8) 40.0 acres	30 98.4 feet	35 114.8 feet	10 32.8 feet
(17) Tourism base camps	D	3.5.2 (1) 4.13.11	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 32.8 feet
(18) Tourist camps	D	3.5.2 (1) 4.13.2	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 32.8 feet
(19) Vacation farms	D	4.13.5	4.05 (6)(7) 10.0 acres	16.2 (6)(8) 40.0 acres	30 98.4 feet	35 114.8 feet	10 32.8 feet
(20) Veterinary clinics and hospital, including large animal boarding	D	--	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 32.8 feet
<i>Municipal, Recreational, Institutional and Other Uses</i>							
(1) Airports and airstrips	D	--	(9)	--	--	35 114.8 feet	10 32.8 feet
(2) Cemeteries and crematoria	D	--	--	--	--	--	3 9.8 feet
(3) Community halls	P	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 32.8 feet	10 32.8 feet
(4) Detention centres and correctional institutions	D	0.4 1.0 acre	--	30 98.4 feet	35 114.8 feet	10 32.8 feet	10 32.8 feet

TABLE 6-1:
A - AGRICULTURE DISTRICT DEVELOPMENT STANDARDS

		Development Standards					
		Subject to Permitted or Disciplinary Actions	Minimum Site Area (ha)	Maximum Site Width (m)	Minimum Front Yard (m)	Minimum Side Yard (m)	Minimum Rear Yard (m)
Use		P	--	--	--	3 9.8 feet	3 9.8 feet
(5)	Historical and archeological sites		--	--	--	--	--
(6)	Institutional camps	D	3.5.2 (1)	0.4 1.0 acre	30 98.4 feet 114.8 feet	35 32.8 feet	10 32.8 feet
(7)	Municipal facilities	P	--	--	--	--	3 9.8 feet
(8)	Parks and playgrounds	P	--	--	--	--	3 9.8 feet
(9)	Places of worship	D	3.7.4 (2)	0.4 1.0 acre	30 98.4 feet 114.8 feet	35 32.8 feet	10 32.8 feet
(10)	Public works, excluding solid and liquid waste disposal sites	P	--	--	--	--	3 9.8 feet
(11)	Radar stations	D	--	1.0 2.47 acres	--	35 114.8 feet 32.8 feet	10 32.8 feet
(12)	Recreation facilities	D	3.7.4 (2)	0.4 1.0 acre	30 98.4 feet 114.8 feet	35 32.8 feet	10 32.8 feet
(13)	Schools and educational facilities	D	--	0.4 1.0 acre	30 98.4 feet 114.8 feet	35 32.8 feet	10 32.8 feet
(14)	Solid and liquid waste disposal facilities, sewage lagoons, pesticide container collection sites, including soil farms for the rehabilitation of contaminated soils, and associated facilities	D	3.5.2 (6) 4.13.4 Table 7-1	0.4 1.0 acre	30 98.4 feet 114.8 feet	35 32.8 feet	10 32.8 feet
(15)	Telecommunications facilities	D	--	1.0 2.47 acres	--	35 114.8 feet 32.8 feet	10 32.8 feet
(16)	Wildlife and ecological conservation areas	P	--	--	--	--	3 9.8 feet
(17)	Wind energy facilities, including wind farms	D	3.5.2 (9) 4.13.17 4.13.18	Development Standards as laid out in Section 4.13.17 & 4.13.18			

Use Designations:

(P) - Permitted Use

Means a use or form of development allowed as of right in a zoning district, subject to the regulations contained in this Bylaw.

(D) - Discretionary Use

A use or form of development specified in this Bylaw, which may be allowed following application to, and approval by Council; and which complies with the development standards and other regulations as may be required by Council and/or contained in this Bylaw.

Special limitation and standards regarding Table 6-1 and the A - Agriculture District:

- (1) where rear yard abuts a railway or a railway reserve, no rear yard may be required in consultation with the railway authority/owner
- (2) or a lesser amount as identified in Section 6.1.9 of this Zoning Bylaw
- (3) accessory dwelling units includes: farm dwellings, business dwellings, garden suites, and communal dwellings
- (4) accessory dwelling units attached to a principal use, such as business dwellings, shall meet the development standards of the principal use to which they are attached
- (5) the same as farm operations
- (6) or a greater or lesser site size as identified in as identified in Section 6.1.10 of this Zoning Bylaw
- (7) unless developed ancillary to a farm operation, in which case 64 hectares, and subject to⁽²⁾ above
- (8) no maximum shall apply if developed ancillary to a Farm Operation
- (9) Private facilities: 1.01 hectares; Publicly-owned facilities: no minimum

6.2 CR1 – LOW DENSITY COUNTRY RESIDENTIAL DISTRICT

6.2.1 Intent

The objective of the **CR1** - Low Density Country Residential District is to provide for low density, multiple lot country residential development and other compatible development in specific areas with standards for such development which does not directly support agriculture.

6.2.2 Permitted and Discretionary Uses and Development Standards

The permitted and discretionary uses and applicable development standards are laid out in Table 6-2.

6.2.3 Prohibited Uses

Uses prohibited in **CR1** - Low Density Country Residential District are as follows:

6.2.4 Accessory Buildings

- (1) Accessory buildings and uses, except dwelling units, shall be permitted and are subject to Section 4.13.1.

6.2.5 Regulations

(1) Site Requirements

The minimum and maximum site size and yard requirements are shown in Table 6-2.

(2) Keeping of Animals

- (a) Large animals, which include only horses, cattle, sheep, goats, llamas and alpacas will be permitted in numbers not exceeding 4 animal units, on a site of at least 4 ha. All other animals shall be limited to domestic pets of the residents of the site, but in no case shall the numbers exceed that equal to one animal unit.
- (b) Animals shall not be pastured within 15 metres of any dwelling not owned by the operator of the pasture or owner of the animals, and no buildings or structures intended to contain animals shall be located within 30 metres of a property line.
- (c) The use of vacant residential sites for pasture of animals is prohibited.

6.2.6 Standards for Discretionary Uses

Council will consider discretionary use applications in the **CR1** - Low Density Country Residential District with regard to Section 3.7.2 Discretionary use Evaluation Criteria and Section 3.7.3 Terms and Conditions for Discretionary Use Approvals as well as additional development standards noted as follows.

(1) **Home Based Businesses**

- (a) Home based businesses are subject to Section 4.13.10 of this Bylaw.
- (b) No home based business in this district shall include auto body repair or repainting operations.
- (c) No heavy construction or industrial equipment or supplies shall be stored on any site for a home based business in this district.

6.2.7 **Exceptions to Development Standards**

Exceptions to development standards in CRI - Low Density County Residential District, are as follows:

Outside storage, including garbage storage, is subject to Section 4.16 of this Bylaw.

6.2.8 **Outside Storage**

CR1 - LOW DENSITY COUNTRY RESIDENTIAL DISTRICT DEVELOPMENT STANDARDS

		Development Standards						
		Subject to Sections	Permitted or Discretionary	Maximum Site Area (ha)	Minimum Site Width (m)	Minimum Front Yard (m)	Minimum Side Yard (m)	Minimum Rear Yard (m)
Residential Uses								
(1)	Single detached dwellings as a principal use	P	Table 7-1	4.05 (10.0 acres)	8.0 (19.8 acres)	30 98.4 feet	10 32.8 feet	3 9.8 feet
Commercial Uses								
(1)	Bed and breakfast homes	D	4.13.5 (10.0 acres)	4.05 (19.8 acres)	8.0 98.4 feet	30 32.8 feet	10 9.8 feet	3 32.8 feet
(2)	Home based businesses	D	4.13.10 (10.0 acres)	4.05 (19.8 acres)	8.0 98.4 feet	30 32.8 feet	10 9.8 feet	3 32.8 feet
(3)	Daycare centres	D		4.05 (10.0 acres)	8.0 98.4 feet	30 32.8 feet	10 9.8 feet	3 32.8 feet
(4)	Residential care facilities	D	4.13.6 (10.0 acres)	4.05 (19.8 acres)	8.0 98.4 feet	30 32.8 feet	10 9.8 feet	3 32.8 feet
Municipal, Recreational, Institutional and Other Uses								
(1)	Community halls	P		0.4 1.0 acre	--	30 98.4 feet	10 32.8 feet	3 9.8 feet
(2)	Historical and archaeological sites	P		--	--	--	--	3 --
(3)	Libraries	P		0.4 1.0 acre	--	30 98.4 feet	10 32.8 feet	3 32.8 feet
(4)	Municipal facilities	P		--	--	--	--	9.8 feet --
(5)	Parks and playgrounds	P		--	--	--	--	3 9.8 feet --
(6)	Places of worship	P		0.4 1.0 acre	--	30 98.4 feet	10 32.8 feet	3 9.8 feet 32.8 feet
(7)	Public museums	D		0.4 1.0 acre	--	30 98.4 feet	10 32.8 feet	3 9.8 feet 32.8 feet
(8)	Public works, excluding solid and liquid waste disposal sites	P		--	--	--	--	3 9.8 feet --

**Table 6-2
CR1 - LOW DENSITY COUNTRY RESIDENTIAL DISTRICT DEVELOPMENT STANDARDS**

		Development Standards						
Use	Permitted or Discretionary	Subject to Sections	Minimum Site Area (ha)	Maximum Site Area (ha)	Minimum Side Width (m)	Maximum Side Width (m)	Minimum Front Yard (m)	Maximum Rear Yard (m)
(9) Recreation facilities	D	3.7.4 (2)	0.4 1.0 acre	--	30 98.4 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet
(10) Schools and educational facilities	D	3.7.4 (2)	0.4 1.0 acre	--	30 98.4 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet
(11) Wildlife and ecological conservation areas	P	--	--	--	--	--	3 9.8 feet	--
(12) Wind energy facilities (one turbine)	D	4.13.17	Development Standards as laid out in Section 4.13.17					

Use Designations:

(P) - Permitted Use

Means a use or form of development allowed as of right in a zoning district, subject to the regulations contained in this Bylaw.

Special limitation and standards regarding Table 6-2 and the CR1 - Low Density Country Residential District:

(D) - Discretionary Use

A use or form of development specified in this Bylaw, which may be allowed following application to, and approval by Council; and which complies with the development standards and other regulations as may be required by Council and/or contained in this Bylaw.

6.3 CR2 – MEDIUM DENSITY COUNTRY RESIDENTIAL DISTRICT

6.3.1 Intent

The objective of the **CR2** - Medium Density Country Residential District is to provide for medium density, multiple lot country residential development and other compatible development in specific areas with standards for such development which does not directly support agriculture.

6.3.2 Permitted and Discretionary Uses and Development Standards

The permitted and discretionary uses and applicable development standards are laid out in Table 6-3.

6.3.3 Prohibited Uses

Uses prohibited in **CR2** - Medium Density Country Residential District are as follows:

6.3.4 Accessory Buildings

- (1) Accessory buildings and uses, except dwelling units, shall be permitted and are subject to Section 4.13.1.

6.3.5 Regulations

(1) Site Requirements

The minimum and maximum site size and yard requirements are shown in Table 6-3.

(2) Keeping of Animals

- (a) Large animals, which include only horses, cattle, sheep, goats, llamas and alpacas will be permitted in numbers not exceeding 2 animal units, on a site of at least 2 ha. All other animals shall be limited to domestic pets of the residents of the site, but in no case shall the numbers exceed that equal to one animal unit.
- (b) Animals shall not be pastured within 15 metres of any dwelling not owned by the operator of the pasture or owner of the animals, and no buildings or structures intended to contain animals shall be located within 30 metres of a property line.
- (c) The use of vacant residential sites for pasture of animals is prohibited.

6.3.6 Standards for Discretionary Uses

Council will consider discretionary use applications in the **CR2** - Medium Density Country Residential District with regard to Section 3.7.2 Discretionary use Evaluation Criteria and Section 3.7.3 Terms and Conditions for Discretionary Use Approvals as well as additional development standards noted as follows.

Outside storage, including garbage storage, is subject to Section 4.16 of this Bylaw.

6.3.8 Outside Storage

Exceptions to development standards in CR2 – Medium Density County Residential District, are as follows:

- 6.3.7 Exceptions to Development Standards
- (a) Home based businesses are subject to Section 4.13.1 of this Bylaw.
 - (b) No home based business in this district shall include auto body repair or repainting operations.
 - (c) No heavy construction or industrial equipment or supplies shall be stored on any site for a home based business in this district.
- 6.3.8 Outside Storage

CR2 - MEDIUM DENSITY COUNTRY RESIDENTIAL DISTRICT DEVELOPMENT STANDARDS

		Use	Subject to Sections	Permitted or Discretionary	Development Standards						
Minimum Site Area (ha)	Maximum Site Area (ha)	Minimum Site Width (m)	Minimum Front Yard (m)	Minimum Side Yard (m)	Minimum Rear Yard (m)	10 feet	9.8 feet	32.8 feet	32.8 feet	32.8 feet	
Residential Uses											
(1) Single detached dwellings as a principal use	P	Table 7-1	1.0 2.47 acres	4.04 9.98 acres	30 98.4 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	10 32.8 feet
Commercial Uses											
(1) Bed and breakfast homes	D	4.13.5	1.0 2.47 acres	4.04 9.98 acres	30 98.4 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	10 32.8 feet
(2) Daycare centres	D	4.13.10	1.0 2.47 acres	4.04 9.98 acres	30 98.4 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	10 32.8 feet
(3) Home based businesses	D	4.13.6	1.0 2.47 acres	4.04 9.98 acres	30 98.4 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	10 32.8 feet
(4) Residential care facilities	D	4.13.6	1.0 2.47 acres	4.04 9.98 acres	30 98.4 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	10 32.8 feet
Municipal, Recreational, Institutional and Other Uses											
(1) Community halls	P	0.4 1.0 acre	--	--	30 98.4 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	10 32.8 feet
(2) Historical and archaeological sites	P	--	--	--	--	--	--	--	--	--	--
(3) Libraries	P	0.4 1.0 acre	--	--	30 98.4 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	10 32.8 feet
(4) Municipal facilities	P	--	--	--	--	--	--	--	--	--	--
(5) Parks and playgrounds	P	--	--	--	--	--	--	--	--	--	--
(6) Places of worship	P	0.4 1.0 acre	--	--	30 98.4 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	10 32.8 feet
(7) Public museums	P	0.4 1.0 acre	--	--	30 98.4 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	10 32.8 feet
(8) Public works, excluding solid and liquid waste disposal sites	P	--	--	--	--	--	--	--	--	--	--
(9) Recreation facilities	D	3.7.4 (2)	0.4 1.0 acre	--	30 98.4 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet	10 32.8 feet

**Table 6-3
CR2 - MEDIUM DENSITY COUNTRY RESIDENTIAL DISTRICT DEVELOPMENT STANDARDS**

		Development Standards					
Use	Permitted or Discretionary	Subject to Sections	Minimum Site Area (ha)	Maximum Site Area (ha)	Minimum Front Yard (m)	Minimum Side Yard (m)	Minimum Rear Yard (m)
(10) Schools and educational facilities	D	3.7.4 (2)	0.4 1.0 acre	30 98.4 feet	10 32.8 feet	3 9.8 feet	10 32.8 feet
(11) Wildlife and ecological conservation areas	P	--	--	--	--	3 9.8 feet	--
(12) Wind energy facilities (one turbine)	D	4.13.17	Development Standards as laid out in Section 4.13.17				

Use Designations:

(P) - Permitted Use

Means a use or form of development allowed as of right in a zoning district, subject to the regulations contained in this Bylaw.

(D) - Discretionary Use

A use or form of development specified in this Bylaw, which may be allowed following application to, and approval by Council; and which complies with the development standards and other regulations as may be required by Council and/or contained in this Bylaw.

Special limitation and standards regarding Table 6-3 and the CR2 - Medium Density Country Residential District:

6.4 H – HAMLET DISTRICT

6.4.1 Intent

The objective of the H –Hamlet District is to provide for residential development and other appropriate uses in the existing Hamlets of Stranraer and Herschel.

6.4.2 Permitted and Discretionary Uses and Development Standards

The permitted and discretionary uses and applicable development standards are laid out in Table 6-4.

6.4.3 Prohibited Uses

Uses prohibited in H - Hamlet District are as follows:

6.4.4 Accessory Buildings

- (1) Accessory buildings and uses, except dwelling units, shall be permitted and are subject to Section 4.13.1.

6.4.5 Regulations

- (1) *Site Requirements*

The minimum and maximum site size and yard requirements are shown in Table 6-4.

- (2) *Keeping of Animals*

- (a) Large animals, which include only horses, cattle, sheep, goats, llamas and alpacas will be permitted in numbers not exceeding 2 animal units, on a site of at least 2 ha. All other animals shall be limited to domestic pets of the residents of the site, but in no case shall the numbers exceed that equal to one animal unit.
- (b) Animals shall not be pastured within 15 metres of any dwelling not owned by the operator of the pasture or owner of the animals, and no buildings or structures intended to contain animals shall be located within 30 metres of a property line.
- (c) The use of vacant residential sites for pasture of animals is prohibited.

6.4.6 Standards for Discretionary Uses

Council will consider discretionary use applications in the H – Hamlet District with regard to Section 3.7.2 Discretionary use Evaluation Criteria and Section 3.7.3 Terms and Conditions for Discretionary Use Approvals as well as additional development standards noted as follows.

- (1) *Home Based Businesses*

- (a) Home based businesses are subject to Section 4.13.1 of this Bylaw.

6.4.8 Outside Storage

- (1) Residential sites that lawfully existed prior to the passing of this bylaw that do not meet the minimum site width and site area requirements outlined in Table 6-4, shall be deemed to be compliant with the minimum site width and site area requirements of this bylaw.

Exceptions to development standards in H – Hamlet District, are as follows:

6.4.7 Exceptions to Development Standards

- (a) No home based business in this district shall include auto body repair or repairing operations.
- (b) No home based business in this district shall be stored on any site for a home based business in this district.
- (c) No heavy construction or industrial equipment or supplies shall be stored on any site for a home based business in this district.

Table 6-4
H -HAMLET DISTRICT DEVELOPMENT STANDARDS

		Use	Development Standards				
Permitted or Discretionary	Subject to Sections		Minimum Site Area (m)	Minimum Site Width (m)	Minimum Front Yard (m) ⁽¹⁾	Minimum Side Yard (m) ⁽¹⁾	Minimum Rear Yard (m) ⁽¹⁾
Residential Uses							
(1)	Manufactured dwellings	P	450 4844 sq. feet	15 49.2 feet	6 19.7 feet	1.5 4.9 feet	6 19.7 feet
(2)	Single detached dwellings as a principal use ⁽¹⁾	P	Table 7-1 4844 sq. feet	15 49.2 feet	6 19.7 feet	1.5 4.9 feet	6 19.7 feet
Commercial Uses							
(1)	Agricultural equipment, fuel, and chemical supply establishments	D	928 989 sq. feet	30 98.4 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(2)	Agricultural service and contracting establishments	D	928 998 sq. feet	30 98.4 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(3)	Animal kennels	D	928 9989 sq. feet	30 98.4 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(4)	Auto wrecking yards	D	928 9989 sq. feet	30 98.4 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(5)	Automotive sales and services including sales and service of recreational vehicles, mobile homes, farm implements and machinery	D	928 9989 sq. feet	30 98.4 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(6)	Bed and breakfast homes	D	4.13.5 4844 sq. feet	15 49.2 feet	6 19.7 feet	1.5 4.9 feet	6 19.7 feet
(7)	Cannabis retail stores	D	3.7.4 (18) 4.13.28 4.23 225 2422 sq. feet	15 49.2 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(8)	Construction trades	D	928 9989 sq. feet	30 98.4 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(9)	Convenience stores	D	225 2422 sq. feet	15 49.2 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(10)	Daycare centres	D	225 2422 sq. feet	15 49.2 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(11)	Gas bars	D	928 9989 sq. feet	30 98.4 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet

**Table 6-4
H - HAMLET DISTRICT DEVELOPMENT STANDARDS**

Development Standards								
	Use	Subject to Sectioris	Site Area (m ²)	Minimum Site Width (m)	Minimum Front Yard (m)	Minimum Side Yard (m) ⁽¹⁾	Minimum Rear Yard (m) ⁽¹⁾	Permitted or Discretionary
(12)	Home based businesses	D	4.13.10	450 4944 sq. feet	15 49.2 feet	6 19.7 feet	1.5 4.9 feet	6 19.7 feet
(13)	Lumber yards, home improvement centres and building supply establishments	D		928 9989 sq. feet	30 98.4 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(14)	Manufacturing or processing facilities	D		928 9989 sq. feet	30 98.4 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(15)	Personal service establishments	D		225 2422 sq. feet	15 49.2 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(16)	Residential care facilities	D	4.13.6	450 4944 sq. feet	15 49.2 feet	6 19.7 feet	1.5 4.9 feet	6 19.7 feet
(17)	Restaurants	D		225 2422 sq. feet	15 49.2 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(18)	Retail stores	D		225 2422 sq. feet	15 49.2 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(19)	Service stations	D		928 9989 sq. feet	30 98.4 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(20)	Storage yards	D		928 9989 sq. feet	30 98.4 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(21)	Welding and machine shops	D		928 9989 sq. feet	30 98.4 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
Municipal, Recreational, Institutional and Other Use								
(1)	Clubs	D		225 2422 sq. feet	15 49.2 feet	6 19.7 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(2)	Community halls	P		225 2422 sq. feet	15 49.2 feet	10 32.8 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(3)	Historical and archaeological sites	P	--	--	--	--	1.5 ⁽²⁾ 4.9 feet	--
(4)	Libraries	P		225 2422 sq. feet	15 49.2 feet	10 32.8 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(5)	Municipal facilities	P	--	--	--	--	--	--

H -HAMLET DISTRICT DEVELOPMENT STANDARDS

Permitted or Discretionary	Subject to Sections	Minimum Site Area (m)	Development Standards			
			Minimum Site Width (m)	Minimum Front Yard (m) ⁽¹⁾	Minimum Side Yard (m) ⁽¹⁾	Minimum Rear Yard (m) ⁽¹⁾
(6) Parks and playgrounds	P	--	--	--	1.5 ⁽²⁾ 4.9 feet	--
(7) Places of worship	P	225 2422 sq. feet	15 49.2 feet	10 32.8 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(8) Public museums	P	225 2422 sq. feet	15 49.2 feet	10 32.8 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(9) Public works, excluding solid and liquid waste disposal sites	P	--	--	--	--	--
(10) Recreation facilities	P 3.7.4 (2)	225 2422 sq. feet	15 49.2 feet	10 32.8 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(11) Schools and educational facilities	P 3.7.4 (2)	225 2422 sq. feet	15 49.2 feet	10 32.8 feet	1.5 ⁽²⁾ 4.9 feet	6 19.7 feet
(12) Wildlife and ecological conservation areas	P	--	--	--	--	--
(13) Wind energy facilities (one turbine)	D 4.13.17	Development Standards as laid out in Section 4.13.17				

Use Designations:

(P) - Permitted Use

Means a use or form of development allowed as of right in a zoning district, subject to the regulations contained in this Bylaw.

(D) - Discretionary Use

A use or form of development specified in this Bylaw, which may be allowed following application to, and approval by Council; and which complies with the development standards and other regulations as may be required by Council and/or contained in this Bylaw.

Special limitation and standards regarding Table 6-4 and the H Hamlet District:

- (1) for a yard abutting a highway or municipal road allowance, the minimum yard shall not be less than 6 m
- (2) for a yard abutting a residential use without an intervening street, the minimum shall be 3 m

6.5 C1 – COMMERCIAL DISTRICT

6.5.1 Intent

The objective of the **C1** - Commercial District is to provide for general commercial / light industrial and other compatible development in specific areas, with standards for such development.

6.5.2 Permitted and Discretionary Uses and Development Standards

The permitted and discretionary uses and applicable development standards are laid out in Table 6-5.

6.5.3 Prohibited Uses

Uses prohibited in **C1** - Commercial District are as follows:

6.5.4 Accessory Buildings

- (1) Accessory buildings and uses, except dwelling units, shall be permitted and are subject to Section 4.13.1.

6.5.5 Regulations

(1) *Site Requirements*

The minimum and maximum site size and yard requirements are shown in Table 6-7.

6.5.6 Standards for Discretionary Uses

Council will consider discretionary use applications in the **C1** - Commercial District with regard to Section 3.7.2 Discretionary use Evaluation Criteria and Section 3.7.3 Terms and Conditions for Discretionary Use Approvals as well as additional development standards noted as follows.

- (1) All operations shall comply with all regulations of Saskatchewan Environment and Saskatchewan Labour which govern their operation and development.
- (2) An application for a discretionary use approval for a commercial or industrial use is subject to Section 3.5.2 (4) of this bylaw.

6.5.7 Exceptions to Development Standards

Exceptions to development standards in **C1** – Commercial District, are as follows:

6.5.8 Landscaping

Landscaping is subject to Section 4.15 of this Bylaw.

6.5.9 Outside Storage

Outside storage, including garbage storage, is subject to Section 4.16 of this Bylaw.

Table 6-5
C1 - COMMERCIAL AND LIGHT INDUSTRIAL DISTRICT DEVELOPMENT STANDARDS

	Use	Development Standards			Minimum Rear Yard (m)	Minimum Side Yard (m)			
		Subject to Sections	Minimum Site Width (m)	Minimum Front Yard (m)					
Residential Uses									
(1) Business dwellings									
Commercial Uses									
(1) Agricultural implement, recreational vehicle, automobile, marine and manufactured homes sales and service establishments	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet			
(2) Agriculturally related commercial uses	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet			
(3) Agricultural service and contracting establishments	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet			
(4) Auction marts, excluding livestock auctions	D	4.13.14	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet			
(5) Autobody and paint shops	D	3.7.4 (6)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet			
(6) Automotive sales and repair	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet			
(7) Bakeries	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet			
(8) Campgrounds	D	3.5.2 (1) 3.7.4 (9) 4.13.2	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet			
(9) Cannabis production facilities	D	3.7.4 (17) 4.13.27 4.23	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet			
(10) Cannabis retail stores	D	3.7.4 (18) 4.13.28 4.23	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet			
(11) Bus terminals	D	3.7.4 (1)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet			
(12) Car and truck washes	P	3.7.4 (1)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet			
(13) Commercial recreational uses	D	3.7.4 (2)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet			

same as principal use

C1 - COMMERCIAL AND LIGHT INDUSTRIAL DISTRICT DEVELOPMENT STANDARDS

		Development Standards				
Use	Subject to Permitted or Discretionary Situations	Minimum Site Area (m ²)	Minimum Front Yard Site Width (m)	Minimum Side Yard Site Width (m)	Minimum Rear Yard Site Width (m)	Minimum Year Round Site Width (m)
(14) Commercial service establishments	P	930	30	7.5	3	(1)
(15) Convenience stores, with or without gas bars	P	4,13.8 4,13.9	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet
(16) Daycare centres	P	930	30	7.5	3	(1)
(17) Drive-in theatres	P	930	30	7.5	3	(1)
(18) Gas bars	P	4,13.8 4,13.9	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet
(19) Hotels	D	3,7.4 (14)	930	30	15	3
(20) Landscaping establishments	P	930	30	15	3	(1)
(21) Lumber yards, home improvement centres and building supply establishments	P	930	30	7.5	3	(1)
(22) Medical and dental offices	P	930	30	7.5	3	(1)
(23) Motels	D	3,7.4 (14)	10,010 sq. feet	98.4 feet	24.6 feet	9.8 feet
(24) Nurseries, greenhouses and garden centres	P	930	30	7.5	3	(1)
(25) Offices and office buildings	P	930	30	7.5	3	(1)
(26) Parking lots	D	930	30	7.5	3	(1)
(27) Personal service establishments	P	930	30	7.5	3	(1)
(28) Prefabricated building component manufacturing and assembly	D	930	30	7.5	3	(1)
(29) Recycling and collection depots	D	3,7.4 (8)	930	30	7.5	3
		10,010 sq. feet	98.4 feet	24.6 feet	9.8 feet	(1)

C1 - COMMERCIAL AND LIGHT INDUSTRIAL DISTRICT DEVELOPMENT STANDARDS

Use	Subject to Sections	Development Standards					
		Permitted or Discretionary	Minimum Site Area (m ²)	Minimum Site Width (m)	Minimum Front Yard (m)	Minimum Side Yard (m)	Minimum Rear Yard (m)
(30) Repair shops and repair services	D	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(31) Restaurants	P	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(32) Retail food outlets	P	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(33) Retail stores, but not including auction markets	P	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(34) Service stations	P 4.13.9	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(35) Taxidermy and accessory tanning of hides	D	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(36) Temporary work camps	D 4.13.20	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(37) Tourist camps	D 4.13.2	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(38) Training centres	P	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(39) Veterinary clinics and animal hospitals	D	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
Industrial Uses							
(1) Agricultural equipment, fuel and chemical supply establishments, but excluding bulk fuel sales and storage	D 3.7.4 (11)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(2) Asphalt and cement plants, gravel yards, and coal yards	D	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(3) Bulk fuel sales and storage	D 4.13.25	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(4) Construction trades and yards	D 3.7.4 (6)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(5) General Industrial Uses (see Use, General Industrial in Section 2	D	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	
(6) Indoor and outdoor storage rental facilities	D 3.7.4 (8)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)	

C1 - COMMERCIAL AND LIGHT INDUSTRIAL DISTRICT DEVELOPMENT STANDARDS

Development Standards							
Use	Permitted or Discretionary	Subject to Sections	Minimum Site Area (m ²)	Minimum Site Width (m)	Minimum Front Yard (m)	Minimum Side Yard (m)	Minimum Rear Yard (m)
(7) Industrial service operations	D		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(8) Light manufacturing or processing facilities	D	3.7.4 (6)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(9) Transportation, trucking and freight handling establishments	D	3.7.4 (6)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(10) Truck stops	D	3.7.4 (12) 4.13.15	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(11) Warehouse, supply depot and storage establishments	D	3.7.4 (6)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(12) Welding and machine shops	D	3.7.4 (6)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
Municipal, Recreational, Institutional and Other Uses							
(1) Ambulance stations	D	3.7.4 (5)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(2) Community halls	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(3) Historical and archaeological sites	P		--	--	--	--	--
(4) Municipal facilities	P		--	--	--	--	--
(5) Parks and playgrounds	P		--	--	--	--	--
(6) Places of worship	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(7) Public works, excluding solid and liquid waste disposal sites	P		--	--	--	--	--
(8) Recreation facilities	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(9) Wind energy facilities (one turbine)	D	4.13.17					

As laid out in Section 4.14.17

Use Designations:

(P) - Permitted Use

Means a use or form of development allowed as of right in a zoning district, subject to the

(D) - Discretionary Use

A use or form of development specified in this Bylaw, which may be allowed

regulations contained in this Bylaw.

following application to, and approval by Council; and which complies with the development standards and other regulations as may be required by Council and/or contained in this Bylaw.

Special limitation and standards regarding Table 6-5 and the C1 – Commercial and Light Industrial District:

- (1) 10% of the depth of the site

6.6 M1 – INDUSTRIAL DISTRICT

6.6.1 Intent

The objective of the **M1** - Industrial District is to provide for light industrial, heavy industrial and other compatible development in specific areas, with standards for such development.

6.6.2 Permitted and Discretionary Uses and Development Standards

The permitted and discretionary uses and applicable development standards are laid out in Table 6-9.

6.6.3 Prohibited Uses

Uses prohibited in **M1** - Industrial District are as follows:

6.6.4 Accessory Buildings

- (1) Accessory buildings and uses, except dwelling units, shall be permitted and are subject to Section 4.13.1.

6.6.5 Regulations

(1) *Site Requirements*

The minimum and maximum site size and yard requirements are shown in Table 6-9.

6.6.6 Standards for Discretionary Uses

Council will consider discretionary use applications in the **M1** - Industrial District with regard to Section 3.7.2 Discretionary use Evaluation Criteria and Section 3.7.3 Terms and Conditions for Discretionary Use Approvals as well as additional development standards noted as follows.

- (1) All operations shall comply with all regulations of Saskatchewan Environment and Saskatchewan Labour which govern their operation and development.
- (2) An application for a discretionary use approval for a commercial or industrial use is subject to Section 3.5.2 (4) of this bylaw.

6.6.7 Exceptions to Development Standards

Exceptions to development standards in **M1** – Industrial District, are as follows:

6.6.8 Landscaping

Landscaping is subject to Section 4.15 of this Bylaw.

6.6.9 Outside Storage

Outside storage, including garbage storage, is subject to Section 4.16 of this Bylaw.

M1 - INDUSTRIAL DISTRICT DEVELOPMENT STANDARDS

		Development Standards						
		Permitted or Discretionary	Subject to Sections	Minimum Site Area (m ²)	Minimum Side Width (m)	Minimum Front Yard (m)	Minimum Rear Yard (m)	Use
Residential Uses								
(1)	Business dwellings	D	3.7.4 (15)	930 10,010 sq. feet	30	7.5 24.6 feet	3	(1) 9.8 feet
Commercial and Industrial Uses								
(1)	Abattoirs and meat packing plants	D	4.13.24	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(2)	Agricultural equipment, fuel, and chemical supply establishments, excluding bulk fuel sales and storage	D	3.7.4 (11)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(3)	Agricultural implement, recreational vehicle, automobile, marine and manufactured homes sales and service establishments	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(4)	Agricultural product processing	D	3.7.4 (11)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(5)	Agriculturally related commercial	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(6)	Agricultural service and contracting establishments	D	3.7.4 (11)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(7)	Auto body and paint shops	D	3.7.4 (6)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(8)	Asphalt and cements plants, gravel yards, and coal yards	D	3.7.4 (7)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(9)	Auction marts, excluding livestock auction facilities	P	4.13.14	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(10)	Auto-wrecking, junk and salvage yards	D	3.7.4 (13)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(11)	Bulk fuel sales and storage	D	4.13.9 4.13.25	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(12)	Cannabis production facilities	D	3.7.4 (17) 4.13.27 4.23	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(13)	Car and truck washes	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)

M1 - INDUSTRIAL DISTRICT DEVELOPMENT STANDARDS

	Use	Permitted or Discretionary	Subject to Sections	Development Standards			
				Minimum Site Area (m ²)	Minimum Site Width (m)	Minimum Front Yard (m)	Minimum Side Yard (m)
(14) Construction yards	P	3.7.4 (6)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(15) Convenience stores	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(16) Gas bars	P	4.13.8 4.13.9	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(17) General industrial uses	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(18) Grain Elevators	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(19) Grain storage, milling, cleaning and/or drying facilities	D		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(20) Indoor storage rental facilities	D	3.7.4 (8)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(21) Kennels	D	4.13.13	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(22) Landscaping establishments	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(23) Lumber yards, home improvement centres and building supply stores	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(24) Livestock auction facilities	D	3.7.4 (4)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(25) Manufacturing and processing facilities	P	3.7.4 (6)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(26) Mineral resource processing	D	3.7.4 (3)	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(27) Nurseries, greenhouses and garden centres	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(28) Petroleum products storage and wholesale	D	4.13.9	930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(29) Prefabricated building component manufacturing and assembly	P		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)
(30) Processing facilities for petroleum derivatives such as ethanol and biodiesel	D		930 10,010 sq. feet	30 98.4 feet	7.5 24.6 feet	3 9.8 feet	(1)

M1 - INDUSTRIAL DISTRICT DEVELOPMENT STANDARDS

Table 6-6

		Development Standards					
Use	Permitted or Discretionary	Subject to Sections	Minimum Site Area (m ²)	Minimum Width Site (m)	Minimum Side Yard (m)	Minimum Rear Yard (m)	Minimum Side Yard (m)
(31) Railway freight yards	D	3.7.4 (6)	930	30	7.5 24.6 feet	3 9.8 feet	(1)
(32) Refining, processing and storage of petroleum resources and related secondary industrial activity such as electrical generating plants and green houses	D	930	30	7.5 24.6 feet	3 9.8 feet	(1)	
(33) Repair shops and repair services	P	930	30	7.5 24.6 feet	3 9.8 feet	(1)	
(34) Restaurants	P	930	30	7.5 24.6 feet	3 9.8 feet	(1)	
(35) Retail food outlets	P	930	30	7.5 24.6 feet	3 9.8 feet	(1)	
(36) Service stations	P	4.13.7 4.13.9	930	30	7.5 24.6 feet	3 9.8 feet	(1)
(37) Stockyards	D	3.7.4 (4)	930	30	7.5 24.6 feet	3 9.8 feet	(1)
(38) Taxidermy and accessory tanning of hides	D	3.7.4 (6)	930	30	7.5 24.6 feet	3 9.8 feet	(1)
(39) Transloading facilities for oil and gas resources	P	4.13.21	930	30	7.5 24.6 feet	3 9.8 feet	(1)
(40) Transportation, trucking and freight handling establishments	D	3.7.4 (6)	930	30	7.5 24.6 feet	3 9.8 feet	(1)
(41) Truck stops	D	3.7.4 (12) 4.13.15	930	30	7.5 24.6 feet	3 9.8 feet	(1)
(42) Veterinary clinics and animal hospitals	P	930	30	7.5 24.6 feet	3 9.8 feet	(1)	
(43) Warehouse, supply depots, storage yards and establishments	P	930	30	7.5 24.6 feet	3 9.8 feet	(1)	
(44) Welding and machine shops	D	3.7.4 (6)	930	30	7.5 24.6 feet	3 9.8 feet	(1)
Municipal, Recreational, Institutional and Other Uses							
(1) Historical and archaeological sites	P	--	--	--	--	--	--
(2) Municipal facilities	P	--	--	--	--	--	--

M1 - INDUSTRIAL DISTRICT DEVELOPMENT STANDARDS

Use	Subject to Sections Permitted or Discretionary	Development Standards				
		Minimum Site Area (m ²)	Minimum Site Width (m)	Minimum Front Yard (m)	Minimum Side Yard (m)	Minimum Rear Yard (m)
(3) Parks	P	--	--	--	--	--
(4) Public works, excluding solid and liquid waste disposal sites	P	--	--	--	--	--
(5) Wind energy facilities (one turbine)	D	4.13.17				As laid out in Section 4.13.17

Use Designations:

(P) - Permitted Use

A use of land or buildings or form of development that is prescribed as a use in the zoning district that is allowed on a site, subject to the regulations contained in this Bylaw.

(D) - Discretionary Use

A use or form of development specified in this Bylaw, which may be allowed following application to, and approval by Council; and which complies with the development standards and other regulations as may be required by Council and/or contained in this Bylaw.

Special limitation and standards regarding Table 6-6 and the M - Industrial District:

- (1) Where abutting railway or railway reserve, no setback may be required in consultation with the railway authority/owner, otherwise 10% of the depth of the site

7 REQUIRED SEPARATION DISTANCES BETWEEN USES

Table 7-1: Separation Distances Between Uses (in metres)		Municipal Wells	Residential *			Parks, Playgrounds and Recreation Facilities	Urban Municipality
			Single Building Site	Multi-parcel Agricultural Residential or Hamlet	Businesses Providing Overnight Accommodation		
Intensive Livestock Operation	300 – 499 A.U.	1,600	1,600	1,600	1,600	1,600	2,400
	500 – 2,000 A.U.	1,600	1,600	1,600	1,600	1,600	3,200
	> 2,000 A.U.	2,400	2,400	2,400	2,400	2,400	3,200
Liquid Manure from ILO – Directly Injected into the Soil		200	200	200	200	200	200
Manure Spreading from ILO – Solid (not incorporated within 24 hours)		800	800	800	800	800	800
Manure Spreading from ILO – Solid (incorporated within 24 hours)		400	400	400	400	400	400
Manure Spreading from Farm Operation which is not an ILO		100	100	100	100	100	100
Aggregate Extraction		--	400	800	400	--	800
Waste Disposal Facilities	Solid	1,600	457	457	457	457	457
	Liquid	1,600	457	457	457	457	457
Anhydrous Ammonia	Non-refrigerated	305	305	305	305	305	305
	Refrigerated	600	600	600	600	600	600
Hazardous Industrial		1,600	1,600	1,600	1,600	1,600	2,400

Distances are measured as follows: between closest point of nearest:

- (1) Single residential property line...
- (2) Multi-parcel or hamlet residential building site...
- (3) Business proving overnight accommodation...
- (4) Park, playground or recreation facility...
- (5) Urban municipality...
- (6) Intensive livestock operation...
- (7) Aggregate extraction use...
- (8) Solid or liquid waste disposal facility
- (9) Anhydrous ammonia storage facility...
- (10) Hazardous Industrial site...
- (11) Manure spreading area...

} ... to the nearest residential property line, corporate limit, ILO, gravel pit, anhydrous ammonia storage facility, waste management facility, or to the site lines for other uses.

* All residences existing as of the adoption date of this bylaw are exempt from the separation distances required in Table 7-1. Any existing residences exempt from these separation distances, and which are damaged or destroyed by an occurrence such


- * Council may reduce the prescribed distances contained in Table 7-1 where:
 - (i) the land being separated is located in another Rural Municipality;
 - (ii) the Council of the other affected Rural Municipality is consulted prior to approval of the proposed development; and
 - (iii) appropriate fencing, screening, landscaping, building and site orientation, road upgrading or other development are provided to mitigate potential land use conflicts.
- * Provincial approval that may be required has been obtained.
- * Council may reduce the prescribed distances contained in Table 7-1 where:
 - (i) the land being separated is located in another Rural Municipality;
 - (ii) the Council of the other affected Rural Municipality is consulted prior to approval of the proposed development; and
 - (iii) appropriate fencing, screening, landscaping, building and site orientation, road upgrading or other development are provided to mitigate potential land use conflicts.

8 MAPS

Rural Municipality of
Mountain View No. 318

ZONING
DISTRICT
MAP

ZONING DISTRICTS	
A	AGRICULTURE
CR	COUNTRY RESIDENTIAL
CR2	COUNTRY RESIDENTIAL
H	HAMLET
C1	COMMERCIAL
M1	INDUSTRIAL



* This is the Zoning District Map which
accompanies EBay Number
View No. 318

Reeve _____

Rural Administrator _____


* Approved on the _____ day of _____

Minister
Saskatchewan Government Relations

**CROSBY
HANNA
& ASSOCIATES**
LANDSCAPE ARCHITECTURE
COMMUNITY PLANNING

4072 - 1st Ave. North
Saskatoon, SK S7K 7S2
www.crosbyhanna.ca
T 306 652-3441
F 306 652-2611

DATE:
March 2017
PROJ.#:
CHA 16965




Sheet 1 of 3

Rural Municipality of
Mountain View No. 318

ZONING
DISTRICT
MAP

ZONING DISTRICTS

A	AGRICULTURE
CRI	COUNTRY RESIDENTIAL
CR2	COUNTRY RESIDENTIAL
H	HAMLET
C1	COMMERCIAL
M1	INDUSTRIAL



* This is the Zoning District Map which
accompanies Bylaw Number
View No. 318

Reeve _____

Rural Administrator _____

* Approved on the _____ day of _____

Minister
Saskatchewan Government Relations

**CROSBY
HANNA
& ASSOCIATES**
LANDSCAPE ARCHITECTURE
COMMUNITY PLANNING
4077 1st Ave North
Saskatoon, SK S7K 7Z5
www.crosbyhanna.ca
T 306.652.3441
F 306.652.3613

DATE:
March 2017
RECORDED IN:
CHAI 6596



Sheet 2 of 3


0 25 50 100 m

Rural Municipality of
Mountain View No. 318

ZONING
DISTRICT
MAP

ZONING DISTRICTS

A	AGRICULTURE
CR1	COUNTRY RESIDENTIAL
CR2	COUNTRY RESIDENTIAL
H	HAMLET
C1	COMMERCIAL
M1	INDUSTRIAL



* This is the Zoning District Map which
accompanies Bylaw Number _____
adopted by the Rural Municipality of Mountain
View No. 318.

Reeve _____

Rural Administrator _____

* Approved on the _____ day of _____

Minister
Saskatchewan Government Relations

**CROSBY
HANNA
& ASSOCIATES**
LANDSCAPE ARCHITECTURE
COMMUNITY PLANNING
TPHG 662-3441
F DNG 622-2611
407C 1st Ave. North
Saskatoon, SK S7K 7T5
www.crosbyhanna.ca

DATE:
March 2017
PROJ.#:
CHA 1606

Sheet 3 of 3
0 25 50 100 200m

